Mup Music Publisher User's Guide



Mup Version 5.3

Mup Music Publisher User's Guide — Mup Version 5.3

CONTENTS

[This page intentionally left blank]

Mup — Music Publisher
User's Guide

1. INTRODUCTION

The music publisher program called "Mup" takes a text file describing music as input, and generates PostScript* output for printing that music. The input file can be created using your favorite text editor, or with the help of the companion Mupmate program, or generated from any other source, such as another program. The input must be written in a special language designed especially for describing music. The majority of the Mup User's Guide is the explanation of this language and how to use it.

Mup has the power to print almost any kind of music, everything from a single melody line to full orchestral or choral scores complete with tempo and dynamic marks. In addition to standard 5-line staffs, it can handle 1-line staffs (typically used for percussion), and tablature notation (typically used for guitar). Because Mup can do so much, it takes a while to master its entire language. However, it has built-in default values for many things, so that you can start using it for simple songs after learning just the basics, then learn the more complicated features as you need them. Mup also has an option to produce output in the standard Musical Instrument Digital Interface (MIDI) format.

Mup is shareware. That means you may try it out before buying it, and that you may make copies for others, but anyone who wants to keep and use Mup must pay a shareware registration fee. Running Mup with the -r option (or /r option for MS-DOS** or Windows**) will print the registration form, with the relevant information. Or if you are using Mupmate, the menu-driven interface on top of Mup, you can get the registration form from the Config Menu. Anyone may download an unregistered copy of Mup via ftp from ftp.arkkra.com or via a Web browser from www.arkkra.com. Music generated by an unregistered copy of Mup will include a notice stating the program is unregistered, but all the features of a registered copy are included.

The User's Guide begins by introducing the basics and describing the general framework of the language. Then it gives detailed information about all the features of Mup. Appendix A gives a sample input file. There is a Quick Reference available that may be useful for jogging your memory after you've had a little experience using Mup.

This User's Guide is for Mup version 5.3.

---

* PostScript is a trademark of Adobe Systems Incorporated

** MS-DOS and Windows are trademarks of Microsoft Corporation

2. MUP BASICS

This section introduces the Mup language, giving some simple examples to give you the flavor of a Mup input file. Subsequent sections will go into greater detail.

2.1 Notes and chords

Music is described one measure at a time. Each note is specified by its pitch value, "a" to "g." As an example, the first measure of "Three Blind Mice" can be described like this:

```
1:    4e; 4d; 2c;
```



The "1:" at the beginning of the line tells Mup that we are describing the notes on staff number 1. In this very simple example, we only have one staff, but later we'll do songs with more than one. Each staff of each measure is normally put on a separate line.

The first three notes of "Three Blind Mice" are E, D, and C. For Mup input, these pitches are given in lower case to avoid having to use the shift key. No octave information was specified in this simple example, so Mup would use its default, which in this case would be the octave beginning with middle C.

The first two notes are quarter notes, and the last note is a half note. Time values of notes are given as shown in the example. A quarter note is marked by a 4, a half note by 2, a sixteenth note by a 16, etc.

A semicolon is used to separate chords. In this simple example, each chord has only a single note in it, but it is possible to have lots of notes in one chord.

At the end of each measure, we have to tell Mup what kind of bar line to draw. The standard bar line is just called "bar." So a complete description of the first measure would be:

```
1:    4e; 4d; 2c;
bar
```

To save typing, Mup allows a lot of shortcuts. One such shortcut is that it assumes that unless you tell it otherwise, each note in the measure is like the note before. You can leave out the second 4, because if you don't specify a time value, Mup will assume the note is the same length as the previous note.

The same sort of idea works with pitches. The third measure of "Three Blind Mice" could be stated like this:

```
1: 4g;8f;;2e;
bar
```



The third note has no information given at all in this example—there is only a semicolon. In this case, Mup will get both pitch and time value from the previous note, so the actual third note in this measure would be an eighth note with pitch F.

You may have noticed that this example doesn't have spaces between chords. There are only a few places where the Mup language requires you to put spaces. However, you can always put some in other places to make things easier to read.

2.2 Parameters

Printed music contains a lot more than just notes and bar lines. Among other things, each staff normally begins with a clef, key signature, and time signature. Mup provides default values for these, which you can then override if you want something different. In the examples so far, we didn't override anything, so Mup would assume its default values, which are treble clef, a key signature with no sharps or flats, and a time signature of 4/4.

There is a long list of "parameters" that can be set. Things like clef and key signature are among them. Parameters can be changed with a line of the form:

parameter_name=value

For example, suppose we have a song written in 6/8 time in the key of D major. We can convey this information to Mup like this:

```
score
  time=6/8
  key=2#

music
  1: 4d;8e;4f;8d;
  bar
```



Note that in this example, the key was specified as two sharps. You can also specify the key by name:

```
  key = d major
```

These parameters give a very different sort of information than the notes of a measure, so they go in a separate section of the input file. Each section of the file describes information for a specific "context." Information about musical notes is given in "music" context, while things that apply in general to the whole score are given in "score" context. Once you start a measure in music context, you have to complete that measure before switching to another context, but otherwise you can pretty much change from one context to another as necessary. Each new context section is headed by its name (e.g., "music" or "score"). At the beginning of input, music context is assumed.

Here is a more complicated example:

```
score
      staffs=2
      key=3&
      time=2/4

music
1: ceg;;
2: 2c;
bar
```



This example starts by setting some parameters. First it states that this piece of music should be printed with two staffs, instead of the default of only one. Then it gives a key signature. Since there is no "flat" symbol on a standard computer keyboard, Mup uses the "&" symbol for flat. The time signature is then set to 2/4.

Next we find the keyword "music," which indicates the end of parameters and the beginning of the music. Data is given for both staff 1 and staff 2. Staff 1 has two chords in the measure. The first is a C minor triad (it's minor since the key is three flats). No time value is specified for this chord. Since it is the very first chord of the piece, Mup cannot use the previous chord's time value, because there is no previous chord. In this case, Mup falls back to using the denominator (bottom number) of the time signature, so the chord is a quarter note. Incidentally, if Mup has to back up to previous notes to deduce pitch and/or time values, it only goes back as far as the beginning of the current measure. That means the default time value for the first chord of every measure in this piece would be quarter note. The second chord on staff 1 is the same as the first, since only a semicolon is specified.

Staff 2 has only a single chord, consisting of a half note with pitch C. Mup checks to make sure the time values on each staff add up to the time signature—no more or less—and will print an error message if they don't. If you have something like a "pickup" measure, which doesn't add up to the time signature, you can specify "space" rather than a chord, to account for the rest of the time.

Some parameters can be set on a per-staff basis as well as for the entire score. Mup also allows for up to three independent voices on each staff, and each voice can have parameters set that apply to only that voice. To get the value of a parameter, Mup always starts at the most specific place it could be defined and works toward the most general. In other words, it will first see if the parameter is set for the current voice. If not, it will see if it is set for the current staff. If not, it will use the value set for the entire score. Staff parameters are set in "staff" context, and voice parameters are set in "voice" context. As an example:

```
score
      staffs=3
      key=1&
staff 2
      key=2&
      clef=bass
music
1: 2f;a;
2: 2c;f;
3: 1f;
bar
```



Staff 2 will have two flats, whereas the other staffs will have one flat. Staff 2 will use the bass clef, whereas the other staffs will use treble clef (since that is the default when none is specified). All the available parameters are listed later in this User's Guide, along with information about whether they can be set for an individual staff or voice, or just for the score as a whole.

2.3 Page headers and footers

Mup allows you to specify a header and/or footer to put on the first page, as well as a header and/or footer to use on subsequent pages. These can include a page number that will be incremented automatically as pages are printed. The headers and footers can be customized as you like, with different fonts and sizes of text and items centered or left or right justified. There is also a shortcut "title" command that can be used to create a canned format title. For example:

```
title "Three Blind Mice"
```

will create a centered title. You can also get left and right justified titles.

2.4 Lyrics

You can specify lyrics for as many verses as you like. They are specified somewhat like notes. As an example:

```
1: 4e;d;2c;
lyrics 1: 4;;2; "Three blind mice,";
bar
```



This example describes the lyrics to go with staff 1. There are three lyric syllables, having time values of quarter note, quarter note, and half note. The actual syllables are given inside the double quotes. Incidentally, since in this example the time values for the lyrics are the same as those of the notes, the time values don't actually need to be specified; if no lyrics time values are given, Mup assumes they match the note time values.

2.5 Miscellaneous

Mup provides a way to print arbitrary text (like "allegro") and musical symbols (like a fermata). It can also print phrase marks, piano pedal marks, etc. The placement of these items is specified in terms of "counts" into the measure. For example:

```
boldital below 1: 3 "mf";
```



tells Mup to print "mf" in bold-italics below staff 1, at count 3 of the measure. You can also print marks associated with specific chords. All of these facilities are described in detail in following sections.

2.6 Displaying, printing, and playing music

Once you have an input file, you can run Mup on it to get the printed version of the music. Entering:

`mup` *myfile*

from a command line prompt or selecting Run > Display from Mupmate will cause Mup to read *myfile*, which should contain text in the Mup input language. If there are no errors in *myfile*, PostScript output will be produced, which can be displayed on the screen or printed via Mupmate or other programs. Mup can also produce MIDI output, which can then be played on your speakers.

If you are using Ghostscript, but without Mupmate, two utility programs are included with Mup for displaying and printing music using Ghostscript. These are described in more detail in the next section.

3. RUNNING MUP

There are two basic ways to run Mup: directly from a command line or via the Mupmate program. You can use either approach, or switch between them as you wish. The Mupmate program just provides a more menu-driven environment on top of the Mup program itself.

You can create a Mup file using any ordinary text editor, and then run the Mup program on the file you created. On Windows, Notepad is a typical editor choice, and on Linux, editors like vim and emacs are commonly used, but pretty much any text editor (not word processor) can be used. Many people, however, prefer to be able to edit, display, and play from a single integrated and more graphical interface, and for them, a helper program called "Mupmate" is provided. The Mupmate program helps lead you through some of the steps, and you can easily access this User's Guide from its Help menu.

3.1 Mupmate

Mupmate is currently only supported on Windows and Linux. However, since the source code is available, and it is based on the cross-platform FLTK toolkit, it would probably be fairly easy to make it run on any system supported by FLTK.

Once you have installed Mup and Mupmate on Windows, double clicking a .mup file in Windows explorer will run Mupmate on that file. Or, you can run Mupmate by going to the Start menu, and choosing Programs, then Arkkra, and then Mupmate. If you would like an icon on the desktop, you can create one by right clicking the Mupmate choice in the Arkkra menu, choosing "copy", right clicking somewhere on the desktop, and choosing "paste".

On Linux, you can just type the mupmate command in a terminal window, optionally followed by the name of a Mup input file. Or you can add mupmate to your favorite window manager's menus.

Mupmate provides five top level menus: File, Edit, Run, Config, and Help. The File menu provides commands for opening new files and saving the file you are working on, as well as exiting the program. The Edit menu provides the kinds of things you would expect in a editor: commands to find a pattern, or find and replace; to select text; to copy, cut, and paste; to go to a specific line; and to undo the previous operation, if you make a mistake or change you mind. The Run menu lets you set runtime options, and then run the Mup program on your input in various ways. You can either just generate a PostScript or MIDI file, or display the PostScript or play the MIDI. The Config menu lets you specify what application program you want to use to view PostScript files and which you want to use to play MIDI files, and well as specify locations for other Mup files. Mupmate will try to find reasonable default values, but you may want to check that they are what you want, and tweak them if they aren't. The Config menu also provides a way for you to fill in the Mup registration form if you wish to send in a paper form rather than registering online via credit card, as well as a place to entry the registration key you will receive once you have paid. The Help menu lets you browse this User's Guide, view some startup hints, or see the current version number of Mup and Mupmate.

Mupmate does not directly provide a print facility. Almost any PostScript viewer already provides this ability, so you can simply select "Display" from the Run menu and use the viewer's print capabilities. Alternately you can use "Write PostScript File" from the Run menu to create a PostScript file that you can print as you would any other PostScript file.

3.2 Mup Options

Mup accepts a number of options. When invoking Mup from a command line, the options are specified by a dash followed by a letter. On Windows/MS-DOS systems, you can substitute a slash instead of the dash. If you are using Mupmate, you will use the "Set Options" form off of the "Run" menu to set the options. You just fill values into the form, and Mupmate will take care of the details of running Mup with your values, so you won't use the dash and letter shown below at all. Some of the options listed below are not available from Mupmate, either because they are meant for debugging, and thus not generally of interest to most users, or because Mupmate handles the appropriate details automatically. The options to the mup command (in alphabetical order) are:

`Command line:` **-c** *N*
`Mupmate:` Run > Set Options > Enable Auto Multirest and Min Measures to Combine

Combine consecutive measures of all rests or spaces into multirests (multiple measures of rest printed as a single measure, usually with the number of measures of rest printed above the staff). Any time there are *N* or more measures in a row that consist entirely of rests or spaces, they will be replaced by a multirest. The combining of measures stops when there is a visible staff that contains notes or lyrics, or that contain text or musical symbols after the first beat of the measure, or when there are parameter changes on a visible staff or in score context that change clef, key, or time signature, or when there is a bar line other than an ordinary bar. This option is most likely to be useful when printing a subset of staffs, where the particular staff(s) you are printing have long periods of rests. See information about the -s option and the "visible" parameter below. This option overrides the restcombine parameter.

`Command line:` **-C**
`Mupmate:` Option not available (only used for debugging).

This option is only used in connection with the -E option. It specifies that comments are to be passed through rather than deleted.

`Command line:` **-d** *N*
`Mupmate:` Option not available (only used for debugging).

Print debugging information. *N* is a bitmap, so you can turn on multiple debugging levels by adding up the flag values. For example, if you want to turn on both level 2 and level 4 tracing, *N* would be 6 (because 2+4=6).

1	input syntax/grammar analysis tracing
2	high level parse phase tracing
4	low level parse phase tracing
8	reserved
16	high level placement phase tracing
32	low level placement phase tracing
64	reserved
128	contents of the main internal list
256	high level print or MIDI phase tracing
512	low level print or MIDI phase tracing

N can be specified in decimal, octal (by using a leading zero), or hex (by using a leading 0x). This information is intended for debugging of Mup itself and thus is not likely to be of use to the average user, and is not available from Mupmate.

`Command line:` **-D** *MACRO[=macro-def]*
`Mupmate:` Run > Set Options > Macro Definitions

Define the macro *MACRO*. The macro name must consist of upper case letters, digits, and underscores, beginning with an upper case letter. The *macro_def* is optional, and gives the text of the macro. On UNIX, Linux, or similar systems, if it contains any white space or other special characters, it must be quoted. On other systems, white space may not be allowed. The -D option can be specified multiple times, if you wish to define more than one macro.

---

* UNIX is a registered trademark of X/Open Company Limited.

`Command line:` **-e** *errfile*
`Mupmate:` Option not needed. Mupmate automatically saves and displays error output.

Place the error message output into *errfile* instead of writing it to the standard error output stream.

`Command line:` **-E**
`Mupmate:` Option not needed (only used for debugging).

Rather than produce PostScript or MIDI output, just expand macros and includes, and write the result to the standard output stream. Comments in the input are deleted, unless the -C option is also specified.

`Command line:` **-f** *outfile*
`Mupmate:` Option not needed. Mupmate automatically creates appropriate output file.

Place the PostScript output into *outfile* instead of writing to the standard output.

`Command line:` **-F**
`Mupmate:` Run > Write PostScript File

This is like the **-f** option, except the name of the output file is derived from the name of the Mup input file. If the name of the Mup input file ends with a ".mup" suffix, the generated PostScript output file will end with a ".ps" suffix instead. If the name of the Mup input file ends with a ".MUP" suffix, the PostScript file will end with a ".PS" suffix. Otherwise, a ".ps" suffix will be appended to the end of the Mup input file name. If multiple input files are listed, the last is used. If none are specified (input is read from standard input), the name "stdin.ps" will be used for the output file.

`Command line:` **-m** *midifile*
`Mupmate:` Option not needed. Mupmate automatically creates appropriate output file.

Instead of generating PostScript output, generate standard MIDI (Musical Instrument Digital Interface) output, and put it in *midifile*. This option also causes the macro "MIDI" to become defined.

`Command line:` **-M**
`Mupmate:` Run > Write MIDI File

This is like the **-m** option, except the name of the MIDI file is derived from the name of the Mup input file. If the name of the Mup input file ends with a ".mup" suffix, the generated MIDI file will end with a ".mid" suffix instead. If the name of the Mup input file ends with a ".MUP" suffix, the MIDI file will end with a ".MID" suffix. Otherwise, a ".mid" suffix will be appended to the end of the Mup input file name. If multiple input files are listed, the last is used. If none are specified (input is read from standard input), the name "stdin.mid" will be used for the MIDI file.

`Command line:` **-o** *pagelist*
`Mupmate:` Run > Set Options > Pages to Display

Print only the pages given in *pagelist*. The *pagelist* can be a comma-separated list of numbers or ranges, where a range is two numbers separated by a dash. For example, -o1,7-9,12-14 would print pages 1, 7, 8, 9, 12, 13, and 14. Alternately, the *pagelist* can be the special keyword "odd" or "even" which will cause all odd or even numbered pages to be printed. This may be useful if you have a printer that only makes single-sided copies, but you wish to print Mup output double-sided. You could print odd-numbered pages, then turn the paper over and feed the pages through again for the even-numbered pages. Pages will be printed in the order specified, so you can print pages in other than ascending order if you wish, or even print the same page more than once. Printing pages in non-ascending order is most likely to be useful when printing more than one page of music on a single physical page, using the panelsperpage parameter.

`Command line:` **-p** *N*
`Mupmate:` Run > Set Options > First Page's Page Number

Start numbering pages at *N* instead of at 1. This can be set inside the Mup input file with the "firstpage" parameter, but the command line option will override the parameter. If **-o** and **-p** are used together, the page numbers given in the **-o***pagelist* must be the printed page numbers. For example, if you use -p10 and want to print just the second page, you would need to specify -o11.

`Command line:` **-r**
`Mupmate:` Config > Registration Form

Print a copy of the Mup shareware registration form to standard output.

`Command line:` **-s** *stafflist*
`Mupmate:` Run > Set Options > Staffs to Display/Play

Only print the staffs that are included in *stafflist*. The *stafflist* can be a comma-separated list of staff numbers or ranges, such as "1,5" or "1-3,7-8" but no spaces are allowed in the list. If the -m or -M option is also used, to produce MIDI output, this option controls which staffs are played rather than which are printed. If you want only a single voice to be printed or played, you can follow a staff number or range with **v1** or **v2** or **v3** to restrict to voice 1, 2 or 3 respectively, such as "1v2" or "1-4v1,5-6v2". Otherwise all voices on the staff are printed or played. You can't specify a list or range for voices; if you only want to make two out of three voices visible, you have to specify them separately, like "1v2,1v3". See also the "visible" parameter.

`Command line:` **-v**
`Mupmate:` Help > About Mupmate

Print the Mup version number. When invoked from command line, Mup will then exit. This document is for version 5.3.

`Command line:` **-x***M***,***N*
`Mupmate:` Run > Set Options > Extract Measures

Extract measures *M* through *N* of the song. This allows you to print or play a part of a song. The comma and second value are optional; if not specified, the default is to go to the end of the piece. Positive values specify the number of measures from the beginning of the piece, while negative values are relative to the end, with -1 referring to the last measure of the song. So -x1,-1 means the entire song, if the song doesn't have a pickup measure. If the song has a pickup measure, that is specified by 0. So for a song with a pickup, -x0,-1 would mean the entire song, and -x0,0 would mean just the pickup measure. As other examples, -x-1,-1 means just the final measure of the song, -x2 means starting after the first full measure, -x3,4 means only measures 3 and 4, and -x6,6 means just measure 6. The starting measure is not allowed to be inside an ending. A common use for this option might be to generate a MIDI file for just a few measures. For example, if you were trying to tweak tempo values for a ritard in the last 2 measures of a song, you could use -x-2 to listen to just those measures.

When invoked from command line, the options, if any, can be followed by one or more *files* in the format described in this User's Guide. If no *files* are specified, standard input is read. If several *files* are listed, they are effectively concatenated together and treated as one big file. Since there are some things (such as header and footer) that are only allowed to occur once, if you have several independent pieces, Mup should be called on each individually rather than trying to print them all with one command. If a specified file does not exist, and its name does not already end with .mup or .MUP, then Mup will append .mup to the specified name and attempt to open that.

If you just want to create a PostScript output file, for printing on a PostScript printer, or viewing with a tool such as GSview, you can use the -f option, as in

```
mup -f outfile.ps infile.mup
```

Or on Unix, Linux or MS-DOS command window, you could redirect the output into a file using the > character, as in:

```
mup infile.mup > outfile.ps
```

For more debugging, in addition to the -d option, if the environment variable MUP_BB is set to "bcfgnsu" or any subset of those letters, the generated output will include "bounding boxes" for the things Mup internally calls bars (b), chords (c), feeds (f), grpsyls (g), header/footer and top/bottom (h), notes (n), staffs (s), and stuff (u). While this is intended for use in debugging Mup itself, it may also help you understand why Mup places things the way it does, since in general, Mup only allows bounding boxes to overlap according to specific rules. If viewed with a color PostScript viewer (not mupdisp, which is covered below), these boxes will be in color.

3.3 Mupdisp and Mupprnt utility programs

If you are using Ghostscript, but prefer to not use Mupmate, there are two utility programs included with Mup for displaying and printing music.

`mupdisp` *Mup_options myfile*

will display music to your screen, while

`mupprnt` *Mup_options myfile*

will print the output to your printer. See the installation instructions for more details on configuring the Mupprnt program for your printer.

The *Mup_options* can be any of the options listed in the section on "Command line arguments" except -C, -E, -f, -F, -m, -M, -r, or -v, which don't send PostScript output to the standard output.

The Mupdisp program allows you to view pages in any order, with either a version small enough to fit on your screen or a near-actual-size version that you can scroll if it doesn't fit on your screen. Mupdisp will run under MS-DOS/Windows or will run under UNIX with TERM of AT386, linux, or xterm (under X windows).

Mupdisp begins in partial page mode, which displays output at approximately actual size (depending on the size of your monitor). In this mode, it is possible that not all of the page fits on the screen, so the scrolling commands can be used to move up and down to view different parts of the page. In full page mode, a small version of the entire page is displayed. This is useful for seeing overall page layout, but is generally too small to see much detail. This mode is now somewhat of a relic of the days when screens were typically much smaller than they are today, and is thus becoming less useful.

Once the music has been drawn on the screen, you can enter various commands to view different pages or parts of the current page. The commands are:

num<Enter> Go to page number *num*.

+ or <space> or <control-E> or <control-F> move forward on the page by about 1/8 of an inch (partial page mode only)

- or <backspace> or <control-Y> or <control-B> move backward on the page by about 1/8 of an inch (partial page mode only)

b or <control-U> or <control-P> or <upward-arrow-key> move backward on the page by about an inch (partial page mode only)

f or <Enter> or <control-D> or <control-N> or <downward-arrow-key> move forward on the page by about an inch (partial page mode only)

h or ? display help screen

m	toggle between partial page and full page modes.
n or <PageDown>	go to next page
p or <PageUp>	go to previous page
q or ZZ	quit
r	Repaint the page (useful for exiting help page)

When in X windows, the mouse can be used for scrolling. The left button scrolls downward like the f command, while the right button scrolls backwards like the b command.

4. MUP FILE STRUCTURE

Mup files do not have to follow any naming convention, although on systems that use file name suffixes to associate a file with an application, it is traditional to use .mup for the suffix. It can also be useful to put a special "magic string" on the first line of Mup files. This magic string is completely optional, but having it there makes it easy for both people and programs to identify the file as Mup input. The standard recommended value for this string is:

```
//!Mup-Arkkra
```

with exactly that spacing and capitalization. If the file uses features of newer versions of Mup, and thus would not work with older versions, you can add a dash and the minimim version number the file requires, as in:

```
//!Mup-Arkkra-5.3
```

4.1 Mup General Syntax

Any number of spaces and tabs can be put in almost anywhere except in the middle of a word. Each statement goes on a separate line. If for some reason you wish to split a statement onto several lines, each but the last must end with a "\" (backslash) character, to tell Mup to treat the next line as a continuation of the current line. Blank lines can be put between statements to make things easier to read.

Comments begin with two slashes and continue to end of line. All comments will be totally ignored by Mup, and are for your own use to remind yourself of something. For example:

```
// Note: in some early manuscripts, this chord had an accent
```

Staffs are numbered from top to bottom, starting at staff 1.

Several different units are used for distances. One is inches or centimeters. (There is a units parameter that is used to select which you want to use.) Another is "stepsizes." One stepsize is half the distance between two staff lines. In the horizontal dimension, "counts" are sometimes used. A "count" refers to the musical duration of a note with a duration of the denominator (bottom number) of the time signature. The actual distance on the page will vary depending on how Mup determines notes should be placed. When you use a time signature with two or more fractions added together, as in 3/4 + 3/8, the "count" is the largest denominator, which would be 8 in the example just given.

Upper and lower case letters are not interchangeable. Thus, for example, "SCORE" is not the same as "score."

Most lines of input end with a semicolon. There are some kinds of input that do not require an ending semicolon, but Mup will allow semicolons on those too, so that if you can't remember if a given command requires a semicolon or not, you can just use one anyway. For the examples in this User's Guide, semicolons are not used when they are not necessary.* Semicolons are not allowed after commands that indicate entering a new context (header, footer, music, staff, grids, etc.). A newline after those commands is optional, although often a good idea for readability.

In music context, newlines are required to separate commands: music data, bar lines, rolls, commands to print strings, dynamic marks, lyrics, etc. all must each end with a newline. In grids context and headshape context, each pair of strings must end with a newline. In other contexts, there are a few cases where newlines between commands are optional, although you may wish to use them anyway to improve readability.

Mup supports macros and conditionals (like 'if' and 'ifdef') that can be placed anywhere in input, except in the middle of words, numbers, or strings; they needn't be on separate lines.

---

* The commands on which the ending semicolon is optional are: bar, multirest, setting of parameters, print, left, right, center, title, newscore, newpage, line, and curve. These commands are described in subsequent sections of this User's Guide.

In a number of statements, Mup expects a text string. All strings must be enclosed in double quotes. For example:

```
"This is a string."
"Allegro"
```

A string can contain any combination of letters, numbers, spaces, and punctuation. It can also contain various things that will cause printing of special music characters, change font and size, and so forth. Those things are covered in the chapter on text strings.

4.2 Contexts

There is always a current Mup "context" that is in effect. When Mup begins reading input, it is operating in "music" context, which is where music, lyrics, barlines, and other related things are described. You can change to another context by entering its name. A context remains in effect until another context is named. The contexts are:

header to define what goes at the top of the first page, typically the title, composer, etc.

footer to define what goes at the bottom of the first page, typically a copyright notice, performance notes, etc.

header2 to define what is to be printed on the top of pages after the first page.

footer2 to define what is to be printed on the bottom of pages after the first page.

top to define what is to be printed on the top of page. This gets printed below the header (or header2), if any. If the output is not already at the beginning of a new page, a new page is started. Unlike header, which can only be used once, and is used only on the very first page, top can be used multiple times. In a song with multiple movements, you might use top to put a title at the beginning of each movement.

bottom to define what is to be printed on the bottom of page. This gets printed above the footer (or footer2), if any. If the output is not already at the beginning of a new page, a new page is started. Unlike footer, which can only be used once, and is used only on the very first page, bottom can be used multiple times.

top2 to define what is to be printed on the top of pages, after the page that uses "top." If the output is not already at the beginning of a new page, a new page is started.

bottom2 to define what is to be printed on the bottom of pages after the page that uses "bottom." If the output is not already at the beginning of a new page, a new page is started.

block to define a block that contains text rather than music.

score to define parameters that apply to the entire score.

staff *S* to define parameters to be used for staff *S*, where *S* is a number from 1 to 40.

voice *S V* to define parameters for a particular voice *V* on staff *S*. The voice *V* can be either 1, 2, or 3. *S* is a staff number from 1 to 40.

grids to define grids (typically for guitar)

headshapes to define what note head shapes to use for notes of various durations. This context is rarely used, and is described in the chapter on shaped notes.

music to define everything else. This includes notes, lyrics, bar lines, phrase marks, tempo and dynamic marks, etc.

Most contexts are optional. An input file just needs to contain either at least one measure of music or at least one block. The **header, footer, header2,** and **footer2** contexts may be placed anywhere in the file, but each can be used only once. The other contexts may appear any number of times in any order, and the order in which they occur is significant in determining the output produced.

5. BASIC STANDARD MUSIC NOTATION

Music data is given in the "music" context. For each measure, there is usually one line of input for each voice. At the end of the measure, the kind of bar line to be used to end the measure is specified. This section describes the input for generating standard music notation. Mup can also generate tablature notation, and that is covered in the next section.

5.1 Specifying chords

5.1.1 Staff and voice

The description of the music for one voice begins with the staff and voice number, followed by a colon. For example:

```
3 1:
```

indicates that the remainder of the line contains musical information for voice 1 of staff 3. If the "voice" number is omitted, voice 1 is assumed. Thus

```
3:
```

is equivalent to the previous example. Both the staff and voice can be given as a list. This may be useful if several staffs have the same notes, or multiple voices on a staff have the same notes. For example:

```
1-4 2:            // voice 2 of staffs 1, 2, 3, and 4
1,2,4:            // voice 1 of staffs 1, 2, and 4,
1,3,6-7 1-2:      // voices 1 and 2 on staffs 1, 3, 6 and 7
5-8 1,2:    // voices 1 and 2 on staffs 5, 6, 7, and 8
```

If you want notes to go to one voice on some staffs and a different voice on others, this can be specified using an ampersand. For example:

```
1 1 & 3 2:
```

will cause the music to go to voice 1 of staff 1 as well as to voice 2 of staff 3. Various styles can be combined:

```
// Voices 1 and 2 on staff 2,
// as well as voice 2 on staff 4
// and voice 1 on staffs 6, 7, and 9
2 1-2 & 4 2 & 6-7,9 1:
```

It is possible to have up to 40 staffs and up to three voices per staff. While there can be voice crossings, in general voice 1 should be the "top" voice, voice 2 the "bottom" voice, and voice 3 the "middle" or "extra" voice. With the first two voices, Mup tries hard to avoid any "collisions" between notes, rests, and other things. Since voice 3 is an extra voice, there are some cases when overlap with the other voices is basically unavoidable, but there are some techniques discussed later that let you tweak placement when necessary.

As an alternative to this voice-at-a-time input style, there is also a chord-at-a-time input style, which will be covered later.

5.1.2 Chord duration information

The rest of the line contains a list of chords, with a semicolon at the end of each chord. Each chord has a time value. The time values of all the chords in the line must add up to the time signature. Time values are given as follows:

Input	Meaning
1/4	quadruple whole (not valid for notes)
1/2	double whole
1	whole
2	half
4	quarter
8	eighth
16	sixteenth
32	thirty-second
64	sixty-fourth
128	128th
256	256th

Any of these time values can be followed by one or more dots, to indicate a dotted note. Each dot increases the time value by 50% of the preceding note or dot.

It is also possible to specify time as two or more times to be added together. For example, 2+8 would indicate the time of a half note plus the time of an eighth note, or in other words, a half note tied to an eighth note. The expression can also include subtractions, like 2.-16. When subtractions are present, it isn't clear what time values you want Mup to use, so it will start with the largest possible time value and add enough additional chords to add up to the total. For example, if you were to use 1-4, indicating a whole note minus a quarter note, Mup will use a dotted half note, even though there are a number of other ways to represent that total time, such as a half note tied to a quarter note.

If a time value is not specified for the first chord in a measure for a given voice, the default timeunit value is used. You can set the default value using the "timeunit" parameter as described in the "Parameters" section. If that parameter is not set, the default is the denominator (bottom number) of the time signature. For chords after the first, if a time value is not specified, the time value for the previous chord is used.

5.1.3 Notes, rests, or spaces

There are three kinds of "chords." The first type consists of one or more pitches, given by the letters "a" through "g". Parentheses can be placed around the pitch if you want the note to be printed in parentheses. (If the pitch is modified by an accidental or octave, which will be discussed later, those must also be included inside the parentheses.) The second is a rest, which is designated by the letter r. The third type is a "space," designated by the letter s. Space is basically a placeholder that takes up time, but doesn't print anything. It is useful when a certain voice only has notes during part of the measure. It can also be useful for specifying "pickup" measures to account for the time before the first note in the measure. For example:

```
// a pickup measure
1: 2.s;8.c;16d;
bar
1: e;g;e;c;
endbar
```



If all voices contain spaces, no space is actually taken up on output. Most of the time, this will be what you want. For example, when you are using space for a pickup, the space is just to add up to a measure, and you don't want any actual blank space at the beginning of the piece. Once in a while, however, you may want space to actually be allocated on output, perhaps to be able to allow space for some special notation. In that case, you prefix the "s" with a "u" to indicate an uncollapseable space.

If a given voice is omitted for a particular measure, Mup defaults to a measure of space.

5.1.3.1 Measure duration

There is a special duration of "m," which means an entire measure. It can only be used with a rest, space, or "rpt" (repeat). For example:

```
1 1: mr;
1 2: ms;
```

A measure rest looks like a whole rest, but is centered in the measure. It should be used when a whole measure is a rest, regardless of the time signature. However, if you want to force use of a symbol other than the whole rest symbol, you can specify a duration before the mr, and the rest symbol for that duration will be drawn instead.

```
4mr;   // use a quarter rest symbol
1/4mr;  // use a quadruple whole rest symbol
2.. mr;  // use a double-dotted half rest
```

Using "m rpt" will cause the measure repeat symbol to be printed, indicating the measure is just like the previous measure. Measures repeats will automatically be numbered, unless the numbermrpt parameter is set to n. If there is more than one voice, you only need to specify the mrpt on voice 1. If you do specify other voices as well, they must be either a mrpt or ms.

```
1: c;d;e;f;
bar

// another measure just like the first
1: m rpt;
bar

// the space between m and rpt is optional
1: mrpt;
bar
```



5.1.3.2 Accidentals

Each pitch letter in a chord may be followed by an accidental. Valid accidentals are:

Input	Meaning
#	sharp
&	flat
x	double sharp
&&	double flat
n	natural

The accidental can be placed inside parentheses if you want it to be printed within parentheses.

5.1.3.3 Octave

An octave indicator may be specified after the pitch letter or optional accidental. The octave can be specified in either of two ways: absolute or relative. A number from 0 to 9 is used to specify an absolute octave. Octaves run from C up to B. Octave 4 is the octave starting on middle C. Octave 3 is the octave below that, etc. A relative octave is specified by one or more plus or minus signs, and indicates that number of octaves above or below the default octave. For example:

```
c   // c in the default octave
e++ // e two octaves above default octave
f#---    // f# three octaves below default octave
b&6 // b flat in octave 6
```

The default octave can be set using the "defoct" parameter, which is described in the "Parameters" section. If that parameter is not set, the default octave is the octave containing the note associated with the middle line of the staff, based on the current clef. In other words, the default octaves are:

Clef	Octave
frenchviolin	5
8treble	5
treble	4
soprano	4
mezzosoprano	4
alto	4
treble8	3
tenor	3
baritone	3
bass	3

5.1.4 Shorthand notations

If a chord is omitted, the values for the previous chord are reused. This works for pitches, rests, and spaces. For normal, 5-line staffs, the pitches for the first chord of every measure must always be specified, since there is no previous chord.

Putting all these things together, here are some examples:

```
// Two eighth notes, each b#, followed by an eighth
// note d, eighth note e, and half note e, with the
// last 3 notes being in the next higher octave.
1 1: 8b#; ; d+; e+; 2;

// Whole note C-E-G chord in default octave
// for voice 2 of staff 1
1 2: 1ceg;

// Four quarter notes on staff 2, voice 1.
// The last is in the octave above the default octave.
2: 4g; a; b; c+;
```



For 1-line staffs, it is never necessary to specify a pitch, since all notes go on the single staff line. You can, however, specify a pitch if you wish. The pitch will be ignored for the purposes of printing, but will be used for MIDI output. If you don't specify a pitch, it is arbitrarily set to middle C.

5.1.5 Note attributes

There are several optional attributes that can be specified for each note. Any or all of these may appear on any note in any order after the letter, accidental, and octave specifications. They include:

— small note head

— tie

— slurs

— headshape

— location tag

5.1.5.1 Small note head

A note specification can be followed by a "?" to indicate the note is to be printed with a small note head, rather than the normal size. (Note: if you have several notes in a chord and want all of them to be small, the "cue" construct, described later, may be preferable.)

Examples:

```
// print the "e" as a small note
1: 1c e? g;
bar

// make the second note small
1: f; ?; g; ;
bar
```



5.1.5.2 Note tie

A "~" can be used to indicate the note is to be tied to the note of the same pitch in the following chord. That following chord need not be in the same measure, but it must contain a matching note. (Note: if a chord with several notes is to have all the notes tied to the following chord, the "tie" construct described later may be preferable.) The ˜ may be preceded by the word 'dotted' or 'dashed' if you want a dotted or dashed tie; otherwise a normal, solid tie is drawn. The ˜ may be followed by the word 'up' or 'down' to specify the direction for the curve's bulge. If neither is specified, Mup will determine an appropriate direction, so you only need to give a direction if you wish to override Mup's choice.

Examples

```
1: d˜; 8; e˜; ; f;
bar

// tie the g (which also happens
// to be a "small" note)
1: 2g+g?˜; 4eg?;
bar
```



5.1.5.3 Slurs

A note can also be followed by a list of notes to be slurred to, enclosed in angle brackets. A slur will be drawn from the note to each of the notes listed in the angle brackets. The notes inside the brackets are specified by a pitch and optional octave. No accidentals are specified, even if the note to be slurred to has an accidental. Examples:

```
// slur from c of first chord to e of second chord
1: c<e>; e; f; g;
bar

// slur from c+ of first chord to a& of second chord
// and from c+ of first chord to d&+ of second chord
1: 2cc+<ad+>; a&d&+;
bar
```



If there is only one note in the following chord, it isn't necessary to explicitly state it within the angle brackets; "<>" will suffice.

```
// slur from c to d, and f to g
1: c<>; d; f<>; g;
bar
```



The < may be preceded by the word 'dotted' or 'dashed' if you want a dotted or dashed slur, otherwise a normal, solid slur is drawn. The > may be followed by the word 'up' or 'down' to specify the direction for the curve's bulge. If neither is specified, Mup will determine an appropriate direction, so you only need to give a direction if you wish to override Mup's choice.

There are four special "slurs" which are really slides to/from an indefinite note. They are most commonly used on tablature staffs, but are allowed on ordinary staffs too. They are: </n> <\n> <n/> and <n\> for sliding upward into the note, downward into the note, upward out from the note, and downward out from the note respectively. These have to be in angle brackets by themselves, so if you want to have both one of these slides and another slur on the same note, multiple sets of angle brackets must be used, as in

```
1: 2c</n><d>;d;
```

5.1.5.4 Head shape

Sometimes you may want to mix head shapes on a single stem. For example, you might want to use a diamond to designate a harmonic, with other notes in the same chord being normal shape. There will be an entire section on head shapes, so only a simple example is given here. To make a single note have a different head shape, use hs followed by the name of the shape in quotes.

```
1: 2e e+ hs "diam";g;
```

5.1.5.5 Note location tag

Finally, a "location tag" can be associated with a note. This would enable you to draw things relative to the note. A note location tag is set by using an "=" followed by a name. The name can be either:

- a single lower case letter
- an underscore followed by one or more letters, numbers, and underscores in any combination.

The name is arbitrary, and is used as a tag that can be referred to later. Examples:

```
// associate tag p with note e&
3: 2c; e& =p g;

// associate tag _end with note f
2: 1f =_end;
```

5.1.6 Chord attributes

There are optional attributes that are associated with an entire chord rather than an individual note. These are put inside square brackets before the list of notes and the time value. There are several classes of information:

- chord style (grace, cue, diam, or xnote)
- head shape
- symbols to be printed with a chord
- slashes
- stem direction
- stem length
- padding
- chord location tag
- horizontal offset
- rest distance

Each class of information is separated from the other by a semicolon. All classes are optional, and can occur in any order.

5.1.6.1 Chord style

Several chord styles can be specified. Grace note chords are designated by the word "grace," or cue note chords by "cue." Grace notes can be specified as any undotted time value of eighth note or shorter, but are treated as taking no time. The time value given is merely used to specify how many flags or beams to put on the grace note. You can also specify a quarter note grace note, which will be printed as a small, stemless note, as is used to show a "prebend" in guitar music. (Actually, you can force a stem if you want, by specifying a len, as is described later.) Cue notes have time like regular notes, but they are printed smaller. If there are several grace notes in a row, they will be beamed automatically. However, you cannot mix quarter (stemless) grace notes with shorter ones. Cue notes follow the same beaming rules as regular notes.

It is also possible to specify "diam," or "xnote." In the case of "diam," the chords will be drawn with diamond-shaped notes, while with "xnote," the chords will be drawn with X-shaped notes. A diamond shaped note head will be used for xnotes that are half note or longer. Here are some examples:

```
[grace]
[xnote]
[cue; xnote]
[diam]
```

5.1.6.2 Head shape

If you want to have the note heads in a chord use a shape other than the normal shapes, you use hs followed by the name of the head shape in quotes. There will be an entire section on shaped notes, so only the basics are covered here. The xnote and diam described above are really just shorthands for two common head shapes. The method using hs lets you use many other note head styles, such as a slash, or triangle.

```
1: [hs "righttri"]cf; [hs "slash"]fa;
```

The section on shaped notes lists all the builtin head shape names, and explains how you can define your own.

5.1.6.3 Symbols to be printed with a chord

It is possible to specify one or more musical symbols or text strings to be printed with a chord. This is typically used for things like staccato and accent marks. The word "with" is followed by one or more things to print. If there are more than one, they are separated by commas. They will be printed outwards from the notes in the order specified. The "with" list is only allowed on note groups, not rests. The list can include symbols from the following table:

Symbol	Meaning
.	staccato
-	legato
>	accent
^	accent

A quoted string can also be specified (e.g., "ff", "adagio", etc.). This will be printed in the font and size specified by the "fontfamily," "font," and "size" parameters. Any of the special music characters can be printed by using the usual convention, e.g., \(ferm) for a fermata. (This is described in a later section.) However, it is usually preferable to use the printing of text strings relative to beats. This will be described in a later section.

Here are some examples:

```
[with ., -]
[with ^, "\(ferm)"]
[with "sfz"; cue]
```

If the symbols acc_hat, ferm, or wedge are used by themselves in a "with" list item, they are handled specially. If the stem direction is such that the upside down versions of these characters should be used, the upside down version will be used.

5.1.6.4 Slashes

Diagonal lines to be drawn through the stem of the group can be specified using

slash *N*

where *N* is the number of slashes to draw. In the case of grace notes, *N* can only be 1, which will produce a grace note with a slash through it. In the case of other notes, *N* can be 1 or greater, and is used to specify tremolo or repetition of the note group. Examples:

```
[slash 2]
[grace; slash 1]
```

5.1.6.5 Stem direction

The chord stem direction can be specified as "up" or "down". Normally Mup chooses the stem direction, but once in a while you may want to override its choice. There are some restrictions. You cannot specify a direction on grace notes. All chords beamed together and the pair of chords in an alternation pair (described later) must have the same stem direction. Examples:

```
[up]
[down]
```

For voice 3, stem direction works a little differently. By default, the stem direction for voice 3 is up, but for voice 3 on any given staff, when you specify a stem direction, that direction will remain in effect until explicitly changed. Thus, for example, if you want all voice 3 stems on a given staff in an entire song to be down, you only need to specify "[down]" on the first chord.

5.1.6.6 Stem len

Normally, Mup sets stem lengths as appropriate, but sometimes you might want to make a stem longer or shorter than normal. This is done with the keyword "len" followed by a length in stepsizes. Some examples:

```
[ len 14 ]
[ len 7; up ]
```

You cannot specify stem length on chords inside of beams. The len can be set to 0 to produce a note head with no stem at all.

There is a stemlen parameter that can be used to set the default stem length. If you don't want any stems, setting that parameter to 0 is more convenient than setting len to 0 on each chord individually.

On beamed chords, Mup will sometimes shorten a stem slightly from its normal minimum length. By default it will never shorten by more than one stemsize, but there is a stemshorten parameter that lets you adjust how much it will shorten. If you don't want Mup to ever shorten stems, you can set this parameter to zero.

5.1.6.7 Padding

Sometimes it may be desirable to space notes somewhat differently than Mup would normally place them. It is possible to specify "padding" before any note group. This is done by specifying the word "pad" followed by a number of stepsizes of white space padding to add before the chord. The number can be fractional, as in 0.5 or 2.25. For example:

```
[ pad 2.5 ]
```

The padding can also be negative. Padding affects the minimum amount of width allocated to a chord, so you can use positive padding values to force additional room in front of a chord, or negative padding to allow things closer together.

5.1.6.8 Chord location tag

It is possible to set a location tag which is associated with an entire chord rather than an individual note. This tag is specified like location tags for notes, with an "=" followed by a name, but is inside the square brackets rather than after a note.

```
3: 2cf; [=h] egc+;
1: [cue; with >; =_ch] fa;
```

5.1.6.9 Horizontal offset

A horizontal offset can be applied to a chord by specifying "ho" followed by a number of stepsizes. The number can be positive or negative, and can include a fractional part. A positive number will cause the chord to be placed that far right of where the horizontal center of the chord would normally be; a negative number will place it that far to the left. It is also possible to simply specify a "+" or "-" which says to place the chord to the right or left, as close as possible without running into something.

A horizontal offset is most commonly used on the third voice of a staff, although it can be used on other voices too. By default, Mup places third voice chords as close as it thinks is safe for avoiding most collisions. Sometimes it may actually be okay visually to place the chord a little closer than that, or perhaps there is a better "nook" to tuck it into on the left side. By specifying a horizontal offset, you can place chords anywhere you want. Mup makes no checks to avoid collisions when you specify a horizontal offset, so this attribute needs to be used with some care.

Here is an example of the use of horizontal offset and stem direction on voice 3.

```
score
  vscheme=3f

music
1 1: c+;b;a;c+;
1 2: e;d;e;f;
1 3: [ho+1] g; [ho-5.2; down]; [ho-] f; [ho+; up] a;
bar
```



5.1.6.10 Rest distance

Usually Mup's placement of rests is satisfactory, but once in a while you might want to force a rest to be placed a little higher or lower than Mup would place it. You can specify a "dist" which is the number of stepsizes from the center of the staff to place the rest symbol, with positive numbers being above the center and negative numbers below. If the staff is transposed, the placement of the rest symbol will be adjusted accordingly.

```
// The first and last rests are in normal position.
// The second is forced higher, the third is forced lower.
1: r; [dist 6]; [dist -4]; r;
bar
```



5.1.6.11 Repeated attributes

If two or more chords in a row have the same bracketed attributes, there are two shorthand notations. Specifying an empty set of brackets "[]" means to use the same attributes as were specified on the previous chord. The previous chord must be within the same measure. Some examples:

```
1: [cue] 4c;[]d;[grace; slash 1] 8f;2e;
bar

1: d; [with .,-]d; []e; []f;
bar
```



The other shorthand is to put 3 dots after a set of bracketed items. This means to repeat the same bracketed items on all chords for the rest of the measure, or until a new set of bracketed items is specified. If you wish to cancel this before the end of a measure but without specifying a new set, the special set "[-]" can be used.

```
// put staccato marks on all notes
1: [with .]... c; d; e; g;
bar
// put several cue size notes in the middle of a measure
1: c; [cue]... 8d; f; e; g; [-] 4c+;
bar
```



You can use more than one set of backets on a single chord. For example "[len 5][down]" and "[len 5;down]" are equivalent. However, [-] can only be used by itself, and if you want to use [] along with another backeted set of items (to duplicate the items on the previous chord plus add some more), the empty [] needs to be first, before the other set of items.

5.1.7 Mid-measure parameter changes

The group attributes can optionally be preceded by mid-measure parameter changes. This is not used very often, but the most common use is to change the clef in the middle of a measure. There are two other parameters that can also be changed here: defoct and release. The change is enclosed in double angle brackets. After the opening angle bracket is the context to which the changes applies (score, staff, or voice), followed by one or more parameter changes.

```
1: c; e; <<score clef=bass>> 2g;
bar
```



If there is more than one parameter listed, they are separated by semicolons.

```
<< staff clef = tenor ; defoct = 4 >>
```

If you wish to change parameters in more than one context, multiple angle-bracketed items can be given:

```
2-3 2: 2c; <<score release=100>><<staff clef=alto>><<voice defoct=3>> c;
```

If you specify "staff" or "voice" context, the specific staff(s) or voice(s) to which the changes apply is based on which staff(s) or voice(s) are being described on the input line. So in the example above, the clef is changed to alto on staffs 2 and 3, and the defoct is changed to 3 for voice 2 on both of those staffs. The release change applies to the entire score.

5.1.8 Cross-staff stems

Sometimes, on music for instruments that use more than one staff, you may want some of the notes of a chord to be printed on the staff above or below, rather than using a lot of leger lines. You can specify this by putting the word "with" before the notes that are to go on the other staff, and following those notes with "above" or "below" to specify which is the other staff. For example:

```
score
    staffs=2
staff 2
    clef=bass
music

1: 1e+g+c++;
2: cc+; ee+; g with g+ above; with c+c++ above;
bar

1: cc+; g with g- below; e with e- below; with cc- below;
2: 1c-e-g-;
bar
```



The notes for the other staff have to follow the notes on the normal staff in the input. As is shown in the example, it is possible to have *all* the notes on the "other" staff, if you wish. The octave is specified as if the note were on the normal staff; Mup will automatically adjust appropriately for the other staff's clef. Once in a while, Mup may not be able to figure out how to completely avoid colliding with other notes; in that case you can use the horizontal offset that was described earlier.

For MIDI purposes, only the normal staff's key signature and accidentals are considered, so if the other staff has a different key signature or accidentals that should really apply to these notes, you will have to supply accidentals explicitly.

5.1.9 Inter-chord attributes

In addition to the chord attributes that can appear in the square brackets before time and pitch information, there are a few attributes that are specified after the time and pitch information. These are attributes that start or end on the chord but also affect other chords. There are several such attributes:

— chord ties

— chord slurs

— custom beaming

— cross-staff beams

— alternation

— slope

If several of these are specified on a single chord, they may be in any order, separated by commas.

5.1.9.1 Chord ties

If all notes in a chord are to be tied to the following chord, the keyword "tie" can be placed at the end of the chord. As was mentioned earlier, individual notes can be tied using a "~" symbol. Thus:

```
ceg tie;
```

is equivalent to

```
c~e~g~;
```

The word "tie" may be preceded by the word "dotted" or "dashed" to produce dotted or dashed ties, otherwise normal, solid ties are drawn. The word "tie" may be followed by the word "up" or "down" to specify the direction of each curve's bulge. If neither is specified, Mup will determine an appropriate direction, so you only need to give a direction if you wish to override Mup's choice.

You can also produce the effect of tying chords by using additive time values. For example, the following lines produce the same output:

```
1: 2ceg tie;8;;4;  // explicit tie

1: 2+8ceg;8;4;   // tie implied by added time values
```

5.1.9.2 Chord slurs

The keyword "slur" can be placed at the end of a chord to indicate that each note in the chord is to be slurred to the corresponding note in the following chord. In other words, the top note of the chord is slurred to the top note of the following chord, the second from the top note in the first chord to the second from the top note in the second chord, etc. Thus the following 2 measures give equivalent output:

```
1: 2f<d> a<b> c+<d+>; dbd+;
bar

1: 2fac+ slur; dbd+;
bar
```



The chord with the "slur" keyword and the chord that follows it must have the same number of notes. The word "slur" may be preceded by the word "dotted" or "dashed" to produce dotted or dashed slurs, otherwise normal, solid slurs are drawn. The word "slur" may be followed by the word "up" or "down" to specify the direction of each curve's bulge. If neither is specified, Mup will determine an appropriate direction, so you only need to give a direction if you wish to override Mup's choice.

5.1.9.3 Custom beaming

Normally, notes of eighth or shorter duration are automatically beamed according to the specification of the "beamstyle" parameter. Occasionally, you may wish to override the default beaming style for a particular situation. This is done using the "bm" and "ebm" keywords. The "bm" (short for "beam") is placed at the end of the chord which is the first to be beamed. The "ebm" (short for "end beam") is placed at the end of the last chord. Both chords must be in the same measure. If there is any custom beaming specified for a given voice in a given measure, the default beamstyle is turned off for that voice for the entire measure, meaning that only what you explicitly specify to be beamed will be beamed. An example:

```
// The d, e, and f will be beamed together,
// but other 8th notes will not be.
1: 4c; 8; d bm; e; f ebm; g; a;
bar

// First two chords beamed together.
// Second chord is tied to third chord.
1: 8.fa bm; 16gc+ tie, ebm; 2; 8a; g;
bar
```



In the absence of custom beaming, Mup will beam notes together using the beamstyle parameter, if that parameter is set. The beamstyle parameter is a list of time values that add up to a measure. Each time value tells how many chords to beam together. For example, a 2 means to beam a half note worth of chords together, whereas 1.. would indicate that a double dotted whole note worth of chords should be beamed together. Here are some examples of how the beamstyle parameter works.

```
// beam each quarter note worth of notes together,
// breaking the beaming at each quarter note boundary
score beamstyle = 4,4,4,4
music
1: 8c;d;e;f;g;a;b;c+;
bar
1: 8c;d;4e;f;8g;c;
bar

// beam each half note worth of notes together,
// breaking the beaming at each half note boundary
score beamstyle = 2,2
music
1: 8c;d;e;f;g;a;b;c+;
bar
// the middle two eighth notes will not be beamed together,
// because they are on opposite sides of the half note boundary
1: 8c;4d;8e;f;4g;8c;
bar

// beam each whole note worth of notes together
score beamstyle = 1
music
1: 8c;d;e;f;g;a;b;c+;
bar
1: 8c;4d;8e;f;4g;8c;
bar

// in 9/8 time, beam each dotted quarter note worth of notes together
score time = 9/8 ; beamstyle = 4., 4., 4.
music
1: 8c;d;e;d;e;f;e;f;g;
bar
// the eight notes will not be beamed together,
// because they are on opposite side of the dotted quarter boundary
1: 4.c;4d;8e;8f;4g;
bar

// in each measure, beam the first dotted half worth of notes together,
// then beam the remaining dotted quarter worth of notes together
score beamstyle = 2., 4.
music
1: 8c;d;e;d;e;f;e;f;g;
bar

// in each measure, beam the first dotted quarter worth of notes together
// then beam the remaining dotted half worth of notes together
score beamstyle = 4., 2.;
music
1: 8c;d;e;d;e;f;e;f;g;
bar
```

The value of the beamstyle parameter is remembered for any later changes back to the same time signature. For example, suppose you set

```
time=4/4
beamstyle=4,4,4,4
```

then later in the piece switched to

```
time=3/4
beamstyle=4,4,4
```

Then any time you went back to 4/4 or 3/4, the beamstyle you had set for that time signature would automatically be set as well. You could, of course, override the automatic setting with a new beamstyle if you wished.

Normally Mup will break beams whenever it encounters a rest or space, but if you or specify an "r" at the end of the beamstyle parameter, it will beam across rests of eighth note or shorter duration. Similarly, specifying an "s" at the end of the beamstyle parameter will cause it to beam across spaces of eighth note or shorter. Specifying both (in either order) will result in beaming across both. Mup will also beam across eighth note or shorter rests or spaces inside of custom beams.

Sometimes, if there are many short notes beamed together, you may wish to subdivide the beams into smaller groupings, where the outer, or primary beam remains unbroken, but the inner, or secondary beams are broken periodically. When using custom beaming, this is specified by "esbm" ("end subbeam" or "end secondary beam") on the chord after which you want the break to occur. When using beamstyle, parentheses are used to indicate what sets of secondary beams are to be included in a given outer beam.

```
score
beamstyle=(4,4),(4,4)
music

// use the beamstyle parameter
1: 16c;d;e;f; g;a;b;c+; c+;b;a;g; 32f;e;f;e;d;c;d;c;
bar

// use custom beaming
1: 16c bm;d;e;f;g;a esbm;b;c+;c+;b;a;g esbm;f;e;d;c ebm;
bar
```



5.1.9.4 Cross-staff beams

In keyboard music, sometimes notes on adjacent staffs are beamed together. Mup will do this with a variation on custom beaming. A bm and ebm must be specified on both staffs, and in each case the bm is followed by a qualifier: on the first of the two staffs, "bm with staff below" must be specified, while on the second staff you use "bm with staff above". For every point in time for the duration of the beam, one staff must have a chord with notes in it, and the other staff must have a space chord. (This is somewhat different than ordinary, non-cross-staff beams controlled by the beamstyle parameter, where spaces are not allowed unless beaming across spaces is specifically requested.) The two "bm" marks must occur at the same time in the measure. Similarly, the two "ebm" marks must occur at the same time in each staff. Grouping subbeams using "esbm" is not supported on cross-staff beams.

Some examples:

```
1: 8f bm with staff below; a; 4s ebm; 4s bm with staff below; 8b; d ebm;
2: 4s bm with staff above; 8a; b ebm; b bm with staff above; d; 4s ebm;
bar
```



Normally the beam will be drawn between the staffs, but you can force the beam to be above or below all the notes by specifying a stem direction. You can also adjust the appearance of the beam by giving stems lengths for the first and last chords in the beam.

```
1: [up]8f bm with staff below;a;4s ebm;4s bm with staff below;8b;[len 11]d ebm;
2: 4s bm with staff above;8a;b ebm;[down;len 14]b bm with staff above;d;4s ebm;
bar
```



If a cross-staff beam includes tuplets, the tuplet numbers will not be printed. You would have to print them yourself using either a "print" statement or a "boldital" statement.

It is possible for cross-staff beams to collide with other items, such as dynamic marks. In these cases, you may need to move the other items. Another thing you might try is specifying stem lengths to alter where the beams get placed, or printing a blank string between the staffs to cause them to get placed further apart. If you specify a slope, you have to specify it on the staff having notes in the first chord, not the staff with space. Slashes are not allowed on cross-staff beams.

Mup doesn’t directly allow cross-staff grace note beams. However, you may be able simulate the effect by using cue note chords along with invisible time signature changes and possibly invisible bar lines. See the section on "Special uses of invisbar" for more details.

You may want to also look at the section on cross-staff stems, for an alternate way to handles some cases where you might use cross-staff beams.

5.1.9.5 Alternation

Alternation pairs can be specified using "alt *N*" where *N* is a number. An alternation pair is two chords that are to played alternately in quick succession but are not written out as such. This is shown by drawing *N* beams between the stems of the chords. The note value you specify for each chord must be the same, and the time value of each must equal the time taken by the pair. For example, if the pair takes up the time of a half note, each chord would be a half note. Here is an example:

```
// Alternate between c and c an octave
// higher. Total time taken is that of
// a half note. Two "beam"-like lines
// will be drawn to show the alternation.
1: 2c alt 2; 2c+;2g;
bar
```



Alternation is not allowed on cross-staff beams.

5.1.9.6 Slope

On the first chord of a set of chords that are beamed together, you can specify a beam angle from -45 to 45 degrees. This will override whatever angle Mup would have used.

```
1: 8g slope 11; b; g slope 0; b;  g slope -5.75; b;
bar
```



5.1.10 Tuplets

Tuplets are specified by giving a list of chords within curly braces. The ending brace is optionally followed by a side ("above" or "below"). This is followed by a number or pair of numbers, and a semicolon.

The "side" tells Mup whether to print the tuplet number and bracket above or below the chords. It only applies on voice 1 or 2 when the other voice (1 or 2) is nonexistent or a space. If there are at least two voices, the number and bracket will always be put above on voice 1 and below on voice 2. You can always force the side on voice 3. If you don't specify a side for a tuplet, Mup will choose the side that seems best.

The first number is the number that should be printed with the tuplet. If it is followed by an "n" the number (and bracket) will not actually be printed. If it is followed by a "y" the number and bracket will always be printed, unless there is only a single chord in the tuplet, in which case only the number will be printed. If it is followed by "num" the number will always be printed, but the bracket will never be printed. If none of those modifiers are are specified, the number will always be printed, but the bracket will be omitted in cases where all the notes in the tuplet are beamed together and the beam does not include any notes not in the tuplet.

The second number, if any, is separated from the first by a comma, and tells the time unit that the tuplet is to take up. This number can be dotted if necessary. It can also be a time expression, like 2+8, although that is very rarely likely to be useful. If no second number is given, the default is to fit in the next shorter undotted note. For example, three eighth notes would be fitted into the time of a quarter note, or five eighth notes would be fitted into the time of a half note.

Occasionally in music, as a shorthand, a single note or chord is printed with a tuplet number to indicate the note or chord is to be repeated several times as a tuplet. Mup will allow this; simply use a tuplet with only one chord, and add one or more slashes.

Here are some examples of tuplets:

```
// This has a triplet, where 3 eighth
// notes take as much time as a
// normal quarter note.
1: { 8ce; df; eg;}3; 4fa;
bar

// This has a dublet, in which 2 quarter notes
// take the time of a normal dotted quarter
1: { 4f; g; } 2, 4.;8a;
bar

// A quarter note and eighth note that
// make up a triplet the length of a
// normal quarter note,
// with the 3 printed above the notes
1: { 4c+; 8b; } above 3; 4c+;
bar

// A septuplet in the time of a half note
// with the "7" printed below the notes
1: { 8c; b-; c; e; d; f; a; } below 7;
bar

// single chord tuplet
1:  { [slash 1] 4.ceg;}3; 4;
bar
```



5.2 Chord-at-a-time input style

There is an alternate input style, in which you enter music a chord at a time, rather than a voice at a time. In this style, the specification before the colon gives one or more patterns that tells how to map notes to staffs and voices.

Suppose you want to print some music in a style which is common for many traditional hymns: it is to be printed on two staffs, each staff will always have exactly two notes, and the rhythm is exactly the same for all voices. With chord at a time input, you specify, for each note in a chord, which staff and voice to map that note. Since there are four notes in each chord, there will be four mappings listed. You want the bottom two notes to get mapped to staff 2, and the top two notes to staff 1. This is shown as

```
// Bass to staff 2 voice 1
// |    Tenor to staff 2 voice 1
// |    |    Alto to staff 1 voice 1
// |    |    |    Soprano to staff 1 voice 1
[  2 1; 2 1; 1 1; 1 1 ]
```

Each item in the semicolon-separated list tells how to map one note. So the first note in each chord will get mapped to staff 2 voice 1. The second note in each chord will also get mapped to staff 2 voice 1. The third and fourth notes will get mapped to staff 1 voice 1.

Since voice 1 is, as always, the default, this could be written more compactly as just:

```
[ 2; 2; 1; 1 ]
```

If you wanted to input notes from top to bottom instead (in soprano-alto-tenor-bass order, rather than bass-tenor-alto-soprano order), you could use:

```
// Soprano
//    Alto
//       Tenor
//          Bass
[  1; 1; 2; 2 ]
```

If you wanted to use two separate voices on each staff (going back to bottom-to-top order), you could specify:

```
// Bass to staff 2 voice 2
// |    Tenor to staff 2 voice 1
// |    |    Alto to staff 1 voice 2
// |    |    |    Soprano to staff 1 voice 1
[  2 2; 2 1; 1 2; 1 1  ]
```

Now let's put these mappings with music data.

```
score
    staffs=2
    vscheme=2f
staff 2
   clef=bass

music

[ 2; 2; 1; 1 ] : facf;dgfb;2cgec+;
bar

[ 1 1; 1 2; 2 1; 2 2 ] : fcaf;bfgd;2c+egc;
bar
```



In the first measure, the first two notes listed in each chord are mapped to staff 2, voice 1, while the third and fourth notes listed in each chord are mapped to staff 1 voice 1. In the second measure, two voices are used and notes are entered in descending order. Note that each note takes on the correct default octave for whichever staff it is mapped to.

It is also possible to use rests or spaces for some of the voices.

```
score
  key=3&
  vscheme=2f

music

[ 1 2; 1 1 ]: rb; eg; ca; gr;
bar

[ 1 2; 1 1 ]: er; sr; 8sf; se; 4sg;
bar
```



Chord attributes and interchord attributes (like tie, slur, xnote, len, and alt) can be specified just like for voice-at-a-time input. Note attributes (like ? and ˜) apply to the note wherever it gets mapped, and items that apply to the chord as a whole will be applied to all the notes.

```
[1 2; 1 1] : [cue; xnote; len 6] b-e; [with > ] ce& slur; dg~; c?g;
```



It is possible to map a note to more than one place by using ranges, and/or by giving a list of staffs and voices, separated by ampersands. This may be useful, for example, if several voices are in unison. In the next example, the first note in each chord will be mapped to voice 1 of staffs 1 through 3, as well as to voice 2 of staff 1, while the second note in each chord will be mapped to voice 2 of staffs 2 and 3.

```
[ 1-3 1  &  1 2;  2-3 2 ] : ec;fd;ge;af;
```



It is also possible to specify more than one bracketed mapping. Each must include a mapping for a different number of notes. So, for example, if some chords in a measure have two notes and others have three, you can define two maps: one for two notes, and one for three. The example below demonstrates placing alto and soprano as two voices on one staff, but sometimes the alto part splits.

```
// For chords with two notes,
// map the first to staff 1 voice 2 (alto),
// and the second to staff 1 voice 1 (soprano).
// For chords with three notes,
// map the first two notes to staff 1 voice 2
// (first and second alto part),
// and the third to staff 1 voice 1 (soprano).
[ 1 2; 1 1 ] [ 1 2; 1 2; 1 1 ]: cec+;df;eg;a-fc+;
```



If mappings of different chords need to vary by something other than the number of notes in the chord, then you will have to use the voice-at-a-time input style.

Since the mapping specifications can get rather complex, and they may be used many times during a song, it is usually best to define macros for them, and possibly even put the macro definitions in an "include" file. Macros and include files are described in a later section.

You can use the different input styles in different measures of a single song, and use different mappings in different measures. You can even mix the two input styles within a measure, but a given staff/voice can only appear on one line of input per measure. So, for example, you could choose to input staffs 1 and 2 of a song in chord-at-a-time input style, and staff 3 in voice-at-a-time style.

5.3 Bar lines

Each measure must be ended with a "bar" of some kind. There are several kinds:

Keyword	Meaning
bar	ordinary bar line
dblbar	double bar
repeatstart	beginning of repeated section
repeatboth	end of one repeated section and beginning of another
repeatend	end of repeated section
endbar	heavy double bar line used at end of song
invisbar	no bar line printed
restart	end staffs and begin anew

In addition, the bar and dblbar types can be preceded by the word "dashed" or "dotted" to produce dashed or dotted bar lines.

```
1: mr;
bar
1: mr;
dblbar
1: mr;
dashed bar
1: mr;
dotted dblbar
1: mr;
repeatstart
1: mr;
repeatboth
1: mr;
repeatend
1: mr;
endbar
```



When a repeatstart would end up at the end of a score, it will automatically get moved to the beginning of the following score. In that case, it isn't clear what kind of bar line you would like to have put at the end of the original score. By default, Mup will use an ordinary bar, but in some cases—like if the repeatstart begins a new section, or there is also a key change—you might want to have a dblbar instead. You can get a dblbar there by specifying dblbar in parentheses before the repeatstart:

```
(dblbar) repeatstart
```

Actually, you are allowed to specify any bar type in the parentheses, but dblbar or possibly invisbar are probably the only ones likely to be useful. If the repeatstart ends up in the middle of a score, so that it doesn't need to get moved to the beginning of the next score, the parenthesized bar type is not needed, so it is just ignored.

Sometimes music is printed without bar lines. The "invisbar" can be used in this case, to fulfill Mup's requirement to specify some sort of bar after every measure without actually printing bar lines.

The restart is a special kind of bar. It follows immediately after another bar line without any intervening music data. (That is, you can't have any notes. You can use score or staff context things, like changing time or key signature.) It would be most commonly used for something like a short coda.

```
score
    staffs=2
    brace=1-2
staff 2
    clef=bass
music

1-2: c;d;e;f;
rom above 1: 3 "D.C. al Coda";
dblbar

// The restart follows a bar
// without any music data in between.
restart

rom above 1: 1 "Coda";
1-2: f;e;d;c;
endbar
```



There are several optional directives that can follow the bar line keyword. They can be specified in any order and are described below.

5.3.1 Bar line padding

One optional directive is padding. It can be used to force Mup to place extra white space to the left of the bar line. It is specified by the keyword "pad" followed by a number of stepsizes of padding to add. For example:

```
dblbar pad 3
```

would add 3 stepsizes of padding.

5.3.2 Bar line location tag

It is also possible to associate a location tag with a bar line. For example:

```
// Associate tag "_bar6" with bar line
bar =_bar6

// Do double bar with an extra stepsize of
// padding, and associate tag "q"
// with the bar line
dblbar pad 1 =q
```

The y coordinate of a bar line is not very useful. Special rules apply if a bar line happens to be placed at the end of a score. Any locations taken relative to the bar that would be to the right of the bar are treated as if the bar line were at the beginning of the following score, just beyond the clef and time and key signatures, if any.

5.3.3 Endings

First and second endings, etc. can be designated at bar lines. This is done with the keyword "ending," followed by a quoted string to use as the label for the ending that should begin at the bar line. An ending will span bars until either another ending is specified, the piece ends, or the special keyword "endending" is used. Examples:

```
bar ending "1."
repeatend ending "2-3"
endbar endending
```

The ending label will always be forced into 12 point times roman font. If you change font or size or include special characters in the ending label, the output is not likely to be aligned properly.

The "endingstyle" parameter (described in the section on parameters) controls where endings are placed. Endings cannot start at or cross over a restart bar.

5.3.4 Rehearsal marks

Rehearsal letters or numbers can be specified on any bar line. There are four formats:

rehearsal let
rehearsal num
rehearsal mnum
rehearsal "*label***"**

In the first example, a rehearsal letter will be placed on the bar. The first occurrence of this will become rehearsal "A", the next "B", and so forth. The second format works in a similar fashion except that numbers are used rather than letters. With the third format, the current measure number is used. With the last format, any arbitrary string within the quotes will be used. The keyword "rehearsal" can be abbreviated to "reh" if you wish. Only one rehearsal mark is allowed on any one bar, but the types can be mixed throughout the composition. (Note that mixing "num" with "mnum" is likely to be very confusing, however.) The rehearsal marks can be intermixed with other bar options:

```
1: 1c;
dblbar reh num ending "1"
1: 1e;
repeatend pad 1 =_xyz reh let ending "2."
1: 1g;
bar rehearsal "Duet"
1: 1ce;
endbar endending
```



The rehearsal marks are normally put directly above the bar line. However, if the bar line falls at the end of a score, the rehearsal mark will be placed at the beginning of the following score, after the clef, key signature, and time signature. The "endingstyle" parameter (described in the section on parameters) is used to determine which staffs get rehearsal marks. The "rehstyle" parameter specifies whether to put rehearsal marks inside a box or a circle or leave them plain.

The rehearsal keyword may be followed by a specification for *fontfamily*, *font*, and/or (*size*). Once specified, these remain in effect for any future rehearsal marks, until explictly changed. Some examples:

```
bar rehearsal helvetica bold (14) let
repeatend reh newcentury num
invisbar reh rom (10) mnum
```

After all the options listed above, you may specify "dist *N*" where *N* is some number of stepsizes. This will override the dist parameter for determining how close to the staff to place the rehearsal mark. If the number is followed by a "!" Mup will place the mark exactly that far from the top of the staff, even if it overwrites other things; otherwise the value specifies a minimum distance.

```
rehearsal num dist 5     // at least 5 stepsizes away
reh bold "A1" dist 2 !   // exactly 2 stepsizes away
```

5.3.5 Setting the measure number

Mup keeps track of measure numbers automatically, but sometimes you may want to override this to set the current measure number to some specific value. This is done by adding mnum=*number* on a bar line, which will set the current measure number to the given *number*.

```
// Set the current measure number to 50
dblbar mnum=50
```

5.3.6 Setting rehearsal letter or number

If you are using the "rehearsal let" or "rehearsal num" styles, you can set those to specific values too, similarly to how mnum can be set. This might be useful, for example, if you have a single input file that contains multiple songs or movements, and you want the rehearsal marks to start over at the beginning of each song or movement.

The rehearsal number can be set on any bar line using num=*N*, where *N* is a number, typically 1.

```
bar num=1
```

The rehearsal letter can be set in a similar way, using let="*X*" where *X* is either a single upper case letter, A to Z, or two upper case letters, AA to ZZ.

```
dblbar let="A" reh let
```

5.3.7 Hiding time/key signature and clef changes

Generally in printed music, when a time signature or key signature change occurs at the beginning of a score, these changes are also printed at the very end of the previous score, to make it clear there is a change coming up. Mup normally does this, but occasionally you may not want that behavior. Sometimes you may want to make a new score appear like the beginning of a new piece. If you wish to suppress the printing of time signature, key signature, and clef changes at the end of the preceding score, you can use the "hidechanges" keyword on the bar line at which the changes occur. Hidechanges cannot be used on a restart bar.

```
1: c;d;e;f;
bar
// change time/key with normal treatment

newscore
score time=5/4 ; key = 1&
music
1: d;e;f;2g;
// don't show changes at end of previous score
bar hidechanges

newscore

score time=6/4 ; key = 2#
music
1: d;e;f;2.g;
bar
```



5.4 Multirest

Multiple measure rests can be indicated using the "multirest" statement. It is followed by the number of measures of rest. The number must be greater than 1, and no larger than 1000. There must not be any note or lyric information specified for a multirest measure. Examples:

```
multirest 15
bar
1: 2c;4;;
bar
1: 2.c;4r;
bar
multirest 5
bar
```



See also the -c command line option, and the restcombine parameter.

Normally, the number of measures of rest is printed, but it is possible to turn this off using the printmultnum parameter. An alternate notation can be specified using the restsymmult parameter.

5.5 Lyrics

Lyrics are specified in a somewhat similar manner to note groups. Lyrics for each staff are specified with the word "lyrics" optionally followed by a *place*, followed by the *staff number*, followed by a colon, then the timing and syllable information.

The *place*, if specified, can be "above" or "below," to indicate whether the lyrics are to be printed above or below the given staff. The default is below.

The *staff number* can be a single number or list of ranges of numbers. It can also be given as the keyword "all," which will place the lyrics above the top visible staff or below the bottom visible staff.

The place can also be specified as "between *M***&***N*" where *M* and *N* are numbers. This will cause the lyrics to printed approximately halfway between staff *M* and staff *N*. *N* must be exactly one greater than *M*.

```
lyrics 1:
lyrics above 2,3:
lyrics between 1&2, 3&4:
```

If you want the same lyrics above some staffs but below others, you can specify several places and list of staffs, separated by semicolons. For example:

```
lyrics above 1,3 ; below 2,4 ; between 5&6 :
```

After the colon comes a list of time values. Time values are separated by semicolons and are specified as they are for notes: "2" for half notes, "8." for dotted eight, etc.

If the time values for lyrics are the same as the time values for the notes on the staff, the time values need not be specified. If you don't specify them, Mup will derive the appropriate values from the music input. If you list more than one staff, the time values will be derived from the first staff you list. Usually, the time values will be derived from voice 1, but if voice 1 music data doesn't exist or is invisible, or if the lyrics are explicitly specified as "below" and there is a visible voice 2, then voice 2 will be used. Voice 3, if any, is never used for automatically deriving time values for lyrics. Some examples:

```
1: c;d;e;f;
lyrics 1: "The sun will shine";
// The time values will be all quarter notes,
// as derived from the music on staff 1
bar

1: 8g;4.f;4g;a;
lyrics 1: "up-on the earth.";
// The derived time values will be 8;4.;4;;
bar

// In these examples, time values will be taken
// from staff 4, since it is the first one listed.
// In the last case, because "below" is specified explicitly,
// the times will be taken from voice 2
// if there is a visible voice 2; in all the other cases
// it will be taken from voice 1 if voice 1 music
// has been entered and is visible.
lyrics 4,7,9: "for-ev-er";
lyrics above 4-6: "nev-er-more";
lyrics between 4&5,6&7: "this is it";
lyrics below 4,2: "and so forth";
```

The line describing the music from which to derive the times must appear in the input prior to the lyrics line that is deriving the times. If chords in the music are tied or slurred together, Mup will treat those chords as being for a single syllable. However, there may be some circumstances in which the rules Mup uses to derive time values may not yield what you want, in which case you will have to explicitly specify the times for that measure.

Following the time values is a list of one or more verse numbers and lyric strings containing the words of the lyrics. The verse number(s) are given within square brackets. If no verse is specified on the first set of lyrics for a staff and place, verse 1 is assumed. On subsequent lyrics strings for that staff and place, the verse number is assumed to be one more than the previous verse number. Thus you only need to explicitly specify a verse number if you want to skip over a verse or supply them out of order.

Verse numbers need not be consecutive. The staff number and verse number can be given as lists or ranges. Another example:

```
1-2: 4.c+;8c;{4e;f;g;}3;
lyrics below 1-2: 4.;8;{4;;;}3; \
        "This is some-thing else."; \
        [4,5] "How do you like this?"; \
        [2-3,6] "Now try this out too.";
bar
```



In this example, the lyrics will go below staffs 1 and 2. There are 5 syllables. The first is a dotted quarter in length, the second is an eighth, and the last three make up a quarter note triplet. The first string is for verse 1, since no verse number was specified. The second string will be used for verses 4 and 5, and the last string for verses 2, 3, and 6.

You can also specify a verse number of "c" which means the verse is to be centered vertically. This is useful if you have a refrain that is identical for several verses, and you don't want to have it printed multiple times.

```
1: c;;e;;
lyrics 1: ;;2s; [1] "verse one"; [2] "verse two";
lyrics 1: 2s;4;; [c] "The refrain";   // centered lyrics
bar
```



The lyrics string is followed by a semicolon. There must normally be one syllable in the lyrics string for each time value. (There is one exception, discussed later.) Syllables are separated in the lyrics string by white space, a dash, or an underscore.

Sometimes a syllable is to be held out for several counts or over several notes. This can be indicated by dashes or underscores. If the syllable in the lyric string ends with a dash, on output the dash will be placed halfway between the given syllable and the next syllable. If the distance between the two syllables is long, several evenly-spaced dashes will be printed. If a syllable in the lyric string ends with an underscore, an underscore line will be printed from the end of the current syllable to the edge of the last note associated with the syllable.

Here are some examples:

```
// Verse 1. The first two words have the
// duration of a quarter note each.
// The last word lasts a half note.
1: e;d;2c;
lyrics 1: 4;;2; [1] "Three blind mice";
bar
```




```
// examples of above lyrics with dash and underscore
1: 4d<>;e;8g;b;4a;
lyrics above 1: "now_ or nev-er";
bar
```



Mup does its best to figure out where to end dashes or underscores. However, if there isn't a following syllable after a dash or underscore, Mup would extend the dash or underscore to the end of the piece, which may not be what you want. There are a few other cases where Mup may be unable to properly deduce where you had intended an underscore to end. You can manually halt the dash or underscore by adding in an "empty syllable," consisting of "<>". Normally, the angle brackets are used inside lyrics to enclose special non-lyrics items, as will be described a bit later. However, if they are used by themselves with nothing between them, they essentially mean a syllable with no text.

```
1: 2c;4d<>;e;
lyrics 1: "last word._";
bar

1: 4d;e;f;g;
// add empty syllable to end the underscore
lyrics 1: 1; "<>";
bar
```



Occasionally, a single chord is used for more than one syllable. If the syllables are within the same word, it is sufficient to omit the dashes between syllables, so that Mup will treat them as a single syllable. However, if the syllables are in separate words, a "~" can be used in place of a space between the syllables. On output, Mup will replace the "~" with a space and a small, curved line below the space, indicating that the syllables on either side are to be joined. For example:

```
1: b;a;2g;
lyrics 1: ;;2; "man-y~a day";
bar
```



If you don't want the curved line, you can use the special character name "\(space)" instead of a literal space. That special space character is printed like a normal space on output, but is not considered a space for the purposes of determining syllable boundaries. Alternately, a technique using angle brackets, described later, can be used.

If several verses use the same time values, you can specify them all on one input line. For example:

```
1: d;f;a;g;
lyrics 1: [1] "this is verse one"; \
       [2] "this is verse two";
bar
```



In this example, because of the \ at the end of the first line, both verses are effectively on the same input line.

Occasionally, lyrics may occur during only part of a measure. This case can be handled by specifying "space" by using an "s" after time values that have no lyric syllable associated with them. For example:

```
1: 2r;g;
lyrics 1: 2s;; [1] "Now";
bar
```



In this example, the first half note of the measure is a space, so there will be no lyric there. The second half note of the measure will have the word "Now" as its lyric. Note that the "s" does not work quite the same way with lyrics as it does with notes. With notes, "2s;;" would mean two half-note spaces, because the space would be used as default for the following chord where no notes were specified. With lyrics, "2s;;" means a half note space, followed by a half note lyric; the space is not carried forward as a default.

If you don't specify any time values, relying on Mup to derive the time values from the corresponding music time values, any rests and spaces in the music will be translated to lyric spaces. If the first note entered in a chord is tied to or slurred to the following chord, that following chord will also be translated to a lyric space, since you most likely want a single syllable to span both chords in that case.

Occasionally, you may want to print something within a lyric string which isn't really a lyric syllable. The most common example of this would be that you may want to print verse numbers. Other possibilities may include associating a dynamic mark (e.g., "mf") with a particular verse, or marking a section for a subset of the singers (e.g., "Men:" or "Solo:"). These extra things are specified within angle brackets. They can be placed immediately before or after any syllable. Mup will not consider them when lining up the syllable with notes. Normally, it will assume there is enough space to print them rather than reserving space for them. If you want Mup to ensure there is enough space to print them, put a "^" immediately after the "<".

Some examples:

```
1: f;e;d;c;
lyrics 1: "<1. >This is verse one.";
bar
1: 2g;4;;
lyrics 1: 2s;4;; "<^\f(TX)ff\f(PV) >Loud-er";
bar
```



The < > construct can also be used to fine-tune the placement of syllables. The placement of syllables is governed in general by the lyricsalign parameter. Sometimes, however, you may want to adjust the placement of specific syllables. Suppose you have a long syllable, like "strength" and would like to shift it leftward somewhat. Entering it as "<str>ength" would cause Mup to move the syllable farther to the left than it normally would.

```
1: c;d;e;f;
lyrics 1: "This strength not moved."; \
        "This <str>ength was moved.";
bar
```



Angle brackets may also be useful for entering chant, where many words are to be associated with a single note. For example:

```
lyrics 1: "All<^ these words will be treated like one syllable.>";
```

The font and size to use for lyrics is initially determined from the "lyricsfontfamily," "lyricsfont" and "lyricssize" parameters for the appropriate staff. If "all" is used for the staff number, the score parameters are used. In the case of "between," the parameters for the staff above are used for determining the font and size. The usual \f and \s forms can be used to change these values for a given verse. Lyrics fontfamily, font and size values are maintained separately for each combination of staff number, verse number, and place, and are carried forward from one measure to the next. Thus, for example, if you want one verse to be printed in roman and another in italics (perhaps one is in English and the other in another language), you need only put a "\f(TI)" at the beginning of the syllable string for the first measure of the second verse, and all subsequent syllables for that verse will be in italics. Setting the "lyricsfontfamily," "lyricsfont" or "lyricssize" parameters will reset the values for all verses of the staff (if set in staff context), or the entire score (if set in score context).

Another way to align a syllable in a particular way is to precede the syllable with a |. If the | is preceded by a number (optionally signed), the left edge of the syllable will be placed that many points from the horizontal "middle" of the chord. If there isn't a number before it, the value is obtained from the sylposition parameter. Negative values are to the left, and will usually be what you want. This alignment method is particularly useful for lining up multiple verses, either to get verse numbers to line up or to align words at the beginning of a poetic line. The | goes after anything in angle brackets.

```
1: 8c;d;4e;8e;g;4c+;
lyrics 1: "<1. >|\"How are you?\" -7|He asked her."; \
          "<2. >|\"I am fine,\" -7|She re-plied.";
bar
```



A few more examples of lyrics:

```
1,3-4: c;8e;;4d;r;
2: c+;8g;;4b;;
lyrics between 1&2,3&4: 4;8;;4;s; "This is a test.";
lyrics above 2: 2s;4;; "The end.";
bar
```



6. TABLATURE NOTATION

Mup can print tablature staffs. Tablature notation is commonly used for guitar and several other instruments. Mup supports tablature for 1 to 9 strings.

Mup will automatically create a normal 5-line staff above each tablature staff, giving the equivalant music on that staff. This staff will be referred to as the "tabnote staff." Normally, you will input music just for the tablature staff, and the tabnote staff will be derived from that. However, for any given measure, you can explicitly input music for a tabnote staff, which will turn off the automatic translation for that measure. If you only want either the tab or tabnote staff to be printed, you can mark the other one as invisible (see the "visible" parameter). You should specify the appropriate clef and key signature for the tabnote staff, so that Mup can make the best derivation.

6.1 Specifying a tablature staff

To set up a tablature staff, you use the stafflines parameter. To get a standard 6-line guitar tablature staff, you can just say

```
score
    staffs=2
staff 2
    stafflines = tab
```

There are 2 staffs, because there is both the tablature staff and the automatically generated tabnote staff. The tablature staff is always immediately below the corresponding tabnote staff. Setting the stafflines parameter to "tab" marks staff 2 as a tablature staff.

If you want tablature for an instrument other than a 6-string guitar with standard tuning, you specify the pitches of the strings from top to bottom within parentheses after the "tab." For example:

```
stafflines = tab (e a d& g)
```

would define some instrument that had 4 strings, with the string on the top line of tablature staff being an e string, the next a, the next d flat, and the bottom g. As shown in the example, pitches can include a # or & if necessary. Strings are assumed to be in octave 4 unless otherwise marked. You can specify a different octave by specifying an octave number after the string's pitch (using either an absolute octave number or pluses or minuses). If the instrument has more than one string with the same pitch (even if they are in different octaves), they must be distinguished by adding one or more ' marks after the pitch. The tablature definition for standard guitar is

```
stafflines = tab (e5 b g d a3 e'3)
```

This specifies that the top string on the staff is e in octave 5. The next three strings are in the default octave of 4, and the last two strings are in octave 3. Since there are two different strings with pitch letter of e, the lower e is marked as e'. Note that the octaves given are how they should be printed on the tabnote staff. A standard guitar actually sounds an octave lower than written. If you just use "stafflines = tab" without specifying any strings, Mup not only assumes the standard guitar layout, and prints in the appropriate octave, but it also automatically transposes the MIDI output to the actual pitches an octave lower. If you specify strings explicitly, you will have to specify the octaves and any desired MIDI transposition values yourself. Stated another way,

```
score
    staffs = 2
staff 2
    stafflines = tab
```

is equivalent to

```
score
    staffs=2
staff 2
    stafflines = tab (e5 b g d a3 e'3)
staff 1
    ifdef MIDI transpose = down perfect 8 endif
```

Note from this last example that MIDI is taken from the tabnote staff, not the tablature staff, so MIDI directives should be placed with the tabnote staff.

Mup should be able to handle almost any instrument with up to 9 strings. Several strings can have the same pitch; you just need to distinguish them with ' marks. The strings must be listed in whatever order the strings are to appear on the tablature staff. As another example,

```
stafflines = tab (g3 d3 a2 e2)
```

would define a standard bass guitar. Note that a bass guitar also sounds an octave lower than written, so it should be transposed for MIDI purposes.

6.2 Music input on tablature staffs

Input of tablature is similar to that on regular staffs. Each note in a chord is specified by a string and a fret. So fret 3 on the g string is designated by g3 or fret 0 on the e' string is designated by e'0. If your open string pitch includes an accidental, that would be included as well, so if you had an instrument with an f# string and wanted to play the 6th fret on that string, it would be f#6. Fret numbers can range from 0 to 99. If you want fret numbers to be placed inside parentheses, put parentheses around them in the input. You can also put both the string and fret within a set of parentheses, in which case, the note generated on the tabnote staff will have parentheses around it. Here are some examples of chords:

```
2: d4; d5a3; b0 d(5); e2(b3)g2;
bar
```



Time values are specified just like on non-tablature staffs: a number optionally followed by one or more dots (like 4 or 8..), or a list of such numbers added together (like 2+8), preceding the chord pitches. Tablature staffs follow the same rules as non-tablature staffs for using time values from the previous chord if no time value is specified on the current chord. Similarly, if no notes are specified for a chord, the same notes used in the previous chord are reused. As an example:

```
2: 4.e5; ;8;b2;
bar
```



Since nothing is specified for the second chord, both time value (dotted quarter) and note (e string fret 5) are copied from the first chord. The third chord in the measure has only a time value (an eighth note) so the note (string/fret) is repeated. The final chord has only a note, so the previous time value is used.

Rests and spaces can be specified with r and s, just like on non-tablature staffs. They result in nothing being printed on the tablature staff, and rest or space being printed on the tabnote staff.

6.3 Chord attributes

Any chord on a tablature staff can be preceded by a list of chord attributes in brackets, just like with non-tablature staffs. If you want a chord to be printed with X (for a muffled string) rather than a fret number, use [xnote]. In this case, the fret number will be used only to determine where to put the X on the tabnote staff, and what note to use for MIDI. Using [diam] will have no affect on the tablature staff, but will cause diamond notes to be used on the tabnote staff. Using [grace] or [cue] will cause the fret numbers to printed in a smaller size, and the corresponding notes on the tabnote staff to be printed in a smaller size. Using [slash *N*] will cause *N* slashes to be printed below the chord on the tablature staff, as well as slashes on the corresponding chord on the tabnote staff. You can use the other chord attributes (with, pad, and =tag) just like on a non-tablature staff.

6.4 Ties

From an input point of view, ties work much the same on tablature staffs as on other staffs. On output, tie marks on tablature staffs are normally not printed, and the frets are not printed on the tied-to chord. If a tie goes across to a new score, the frets are printed, but in parentheses, to indicate the chord is really just the continuation of a tie.

6.5 Slides

In Mup input, slides are shown with <>, rather like slurs on non-tablature staffs. There is a special variation used for slides that come from nowhere in particular or go to nowhere in particular. These are shown with <\n>, </n>, <n\>, or <n/>. A slide is indicated on output on tablature staffs as a slanted line between 2 fret numbers on a string. On tabnote staffs, they as drawn as a slanted line between 2 notes. See the examples below:

```
2: a5<>; a6; d3<>; d2;
bar

2: b4</n>; e3<\n>; a2<n/>; e'5<n\>;
bar
```



6.6 Bends

A bend (stretching a string to make it sound higher than normal) is specified on tablature staffs by putting a text string after the string. The text string can be the word "full" or a number and/or fraction. Some examples:

```
2: e4 "full"; e "1/2"; 2e "1 1/2";
bar
```



If you want to bend back down to having no bend (a release), the text string specifying the bend is just an empty string of "". Note that if both a fret and bend other than "" are specified, this indicates a prebend, whereas if only a bend is specified, this indicates a normal bend.

Bends need not be an integer number of half steps, but if you specify a bend that falls between half steps, when it is used on the tabnote staff, the bend is rounded to the nearest half step, or rounded downward if it is exactly in the middle of a half step. When possible, bends of 1/4 step or less are shown on the tabnote staff by a small curve rather than by a separate note.

You can specify bends on more than one string at once, but a continuation bend (bending to a new distance without replucking the string) is only allowed on a single string at a time. Here are some examples:

```
2: g0b2e'0; e' "1/2" g "full" b "3/4"; e' ""; a2;
bar

2: a "1/2"; a "full"; a "1/2"; a "";
bar
```



If you have more than one voice on a tablature staff, bends on other than the top voice may collide with other voices in some cases, and if there are bends from more than one voice simultaneously, they may collide.

On non-tablature staffs, bends are specified with a ^ symbol followed by the note to bend to. The note to bend to is specified by letter and optional octave (accidentals are not specified). If you want just a small bend (1/4 step), this is specified by ^/. For example:

```
1: e ^f; f; b ^c5; c#5;
bar

1: d+^e+ g^a; e+a; g ^/; c ^/ c+^/;
bar
```



6.7 Miscellaneous

Note attributes of ~ for tie, ? for a small note, and = for a tag work the same on tablatures staffs as on non-tablature staffs.

If bm, ebm, or esbm are given on tablature staffs they are transferred to the tabnote staff and used for custom beaming there. Items in "with" lists inside [ ] are also copied to the tabnote staff. In general, unless otherwise specified here, if you want items such as tempo and dynamic marks to appear on both tablature and tabnote staff, you have to specify them for both staffs.

The "alt" inter-chord attribute is not allowed on tablature staffs.

When there is a tablature staff, the MIDI is actually generated from the tabnote staff. There are some limitations. Currently, no MIDI pitch bends are generated; slides and bends are instantaneous rather than gradual.

If a capo is being used, it probably better to declare a transposition of the tabnote staff rather than declaring the strings to be different notes. This is because most people would rather think of the original string letters when entering the tab staff information; and if you decide to put the capo on a different fret later, you only have to change the "transpose" line. The automatic MIDI octave tranposition for standard guitar will also then still apply, on top of your transposition.

If you specify an octave mark (discussed in a later section) on a tabnote staff, the derived music will be printed with the notes raised or lowered the appropriate number of octaves to correspond to the given octave mark interval.

Since ties are not printed on tablature staff, and input notation for tablature slides is like what is used for slurs on ordinary staffs, if you want a curved line like a tie or slur on a tablature or tabnote staff, you have to use a phrase mark. See the section on phrase marks for more details.

The chord-at-a-time input style can also be used for tablature. The staffs being mapped to from a single input line must either be all tablature or all non-tablature, however.

```
score
     staffs=4
     brace=1-2, 3-4
     tabwhitebox=y
staff 2
     stafflines=tab
staff 4
     stafflines=tab
music

// The first two notes in each chord go to staff 2,
// and the last two go to staff 4.
[ 2; 2; 4; 4] : a2d0 g0b3; e'0a2 g0e0; 2 e'0d2 b0e3;
bar
```



7. SHAPED NOTES

If you intend to only use the usual system of note heads, you can skip over this section on shaped notes. If you wish to use less common note head shapes, like X-shaped notes, rather than normal note heads, or want "shaped note" music that is often used for "Sacred Harp" style music, sometimes also called "fasola notation," then this section will explain how you can do that.

7.1 Headshapes context

The headshapes context is used in conjuction with the noteheads parameter to determine what characters will be used when printing note heads. It is rarely necessary to include a headshapes context in your music, since Mup already has the most common values built in, so generally you just need to use the noteheads parameter to access them. However, it is still important to understand what the headshapes context can contain, to understand how the builtin values work.

The headshapes context defines, for a given head shape name, what specific note head characters to use for the notes of various durations. It contains one or more pairs of strings. The first string in the pair gives a name for a set of note head shapes. The second string contains a space-separated list of the names of 4 note head characters to use for that head shape name. The first shape in the list is used for quarter notes and shorter, the second for half notes, the third for whole notes, and the fourth for double whole notes.

If an upside down version of the character is to be used for stem down notes, the name is prefixed by "u?" (The "u" stands for "upside-down" and the question mark is intended to be mnemonic for the fact that the upside down version will only be used part of the time, namely for stem-down notes.)

As was mentioned above, the most common mappings are already built into Mup. Here is the list of the pre-defined values. Pay particular attention to the first string on each line, since those are the names you will use in the notehead parameter and for overriding chord and note shapes.

"norm"	"4n 2n 1n dblwhole"
"x"	"xnote diamond diamond dwhdiamond"
"allx"	"xnote xnote xnote xnote"
"diam"	"filldiamond diamond diamond dwhdiamond"
"blank"	"blankhead blankhead blankhead blankhead"
"righttri"	"u?fillrighttriangle u?righttriangle u?righttriangle u?dwhrighttriangle"
"isostri"	"fillisostriangle isostriangle isostriangle dwhisostriangle"
"rect"	"fillrectangle rectangle rectangle dwhrectangle"
"pie"	"fillpiewedge piewedge piewedge dwhpiewedge"
"semicirc"	"fillsemicircle semicircle semicircle dwhsemicircle"
"slash"	"fillslashhead slashhead slashhead dwhslashhead"
"allslash"	"fillslashhead fillslashhead fillslashhead fillslashhead"

You can redefine these or define new ones if you wish. The name (the first of the two strings in the pair) can be almost anything you want. The four names in the second string must be taken from the list of valid note head characters given below:

4n	2n 1n	dblwhole
filldiamond	diamond	dwhdiamond
fillisostriangle	isostriangle	dwhisostriangle
fillpiewedge	piewedge	dwhpiewedge
fillrectangle	rectangle	dwhrectangle
fillrighttriangle	righttriangle	dwhrighttriangle
ufillrighttriangle	urighttriangle	udwhrighttriangle
fillsemicircle	semicircle	dwhsemicircle
fillslashhead	slashhead	dwhslashhead
xnote		
blankhead		

The righttriangle shape names can be prefixed by u? when used in the headshapes context, to indicate the upside down version of them should be used when the stem is down. Note that u? cannot be used on any other note head characters, since none of the others have a corresponding upside down version.

As an example of how you could use the headshapes context, suppose you wished to use xnote for half notes and shorter, and diamond for longer notes. That is different than either of the builtin values "x" or "allx" but you could override one of them:

```
headshapes
    "x" "xnote xnote diamond diamond"
```

The blankhead does not print any head at all, it just leaves space as if there were a note head. It might be used if for some reason you just want stems.

7.2 Noteheads parameter

The noteheads parameter describes which note head shape to use for each pitch in the scale. It can be specified in score, staff, or voice contexts. If you want to use the same shape for all pitches, (as is the case with standard notation), only one shape name is specified. Thus the default value for this parameter is

```
noteheads = "norm"
```

If you want to use different shapes for different pitches, the noteheads value needs to be a string containing a list of 7 shape names. They are listed from the "tonic" of the major key up the scale, with the key based on the number of sharps or flats in the key signature. The shape names must be from the list of pre-defined head shapes (norm, xnote, diam, blank, righttri, isostri, rect, pie, semicirc, slash), or names that you have given as the first in a pair of strings in the headshapes context.

You can get the most common shaped note system using 4 shapes using:

```
noteheads = "righttri norm rect righttri norm rect diam"
```

There are several shaped notes systems using 7 different shapes. One such system is specified by:

```
noteheads = "isostri semicirc diam righttri norm rect pie"
```

Once the noteheads parameter is set, you specify your music just like you would for standard notation, but Mup will use the appropriate note heads based on your specifications.

```
score
   // Use a 7-shaped system.
   noteheads = "isostri semicirc diam righttri norm rect pie"

   // Noteheads are given in order for the major key,
   // so we'll start out with an example in major.
   key = d major

music

// Do a descending scale in D major
1: d+;c+;b;a;
bar

1: g;f;e;d;
dblbar

score
   // Now we switch to D minor, where the "tonic"
   // will start at the rect and then wrap around.
   key = d minor

music

// Do a descending scale in D minor
1: d+;c+;b;a;
bar

1: g;f;e;d;
bar
```



7.3 Overriding chord note heads

It is possible to override what note shape to use for a chord, by giving "hs" followed by a head shape name from the headshapes context, inside square brackets. Thus

```
[hs "righttri"]
```

would use the "righttri" headshape. The specific character to use would be based on the group's duration. In other words, if the chord was a quarter note or shorter, the "fillrighttriangle" note head would be used, but if the chord was a half or whole note, a "righttriangle" note head would be used, and a "dwhrighttriangle" would be used for a double whole note.

The hs specification can be used along with other things that can go in the square brackets. For example,

```
        [hs "blank"; len 0]
```

would use blankheads and no stem, resulting in no chord being printed at all!

7.4 Overriding individual note heads

If you want to override the note head shape to be used for one specific note in a chord, you use hs followed by the head shape name as a string after the note.

```
1: cg e+ hs "diam"; f a hs "x" c+; 2ge+;
bar
```



7.5 Putting it all together to use shaped notes

In summary, note head shapes can be specified in five different places: per note, per chord, in voice context, in staff context, and in score context. When deciding what note head shape to use, Mup checks for specifications in that order, using the first it finds.

Since fret numbers are used rather than note heads on tablature staffs, the only head shape name that is allowed is "allx." which is used for "muffled" notes.

Here is a simple example of shaped notes, using the common 4-shape system.

```
score
    noteheads = "righttri norm rect righttri norm rect diam"
    staffs=4
    key=2#
    bracket=1-4

staff 3
    clef=treble8
staff 4
    clef=bass
music

1: 2c+;4d+;e+;
2: 2e;4a;f;
3: 2e;4f;c;
4: 2a-;4f-;a-;
bar

1: 1d+;
2: 1f;
3: 1d;
4: 1d;
endbar
```



Here is an example of using the same note head shape for all pitches, illustrating how the proper version—filled or open—of the note head is used, based on the note's duration.

```
score
    time=8/4
    beamstyle=2,2,2,2

music
1: 8cf;;4;2;1;
bar

score noteheads="isostri"
music
1: 4ec+;8;;2;1;
bar

score noteheads="rect"
music
1: 1gc+;4;2;8;;
bar

score noteheads="pie"
music
1: 8cf;;4;2;1;
bar

score noteheads="x"
music
1: 4ec+;8;;2;1;
bar

score noteheads="slash"
music
1: 1gc+;4;2;8;;
bar
```



And finally, here is a somewhat silly example that demonstrates how you can use the various shaped notes features to get any kind of note head that Mup supports anywhere you want.

```
headshapes
	// Make some user-defined head shapes.
	// These combinations don't really make sense;
	// they are just to demonstrate what you can do.
	"reg" "4n 2n 2n 2n"
	"other" "fillrectangle diamond isostriangle dblwhole"

score
	// Set notesheads, using an arbitrary mixture of builtin
	// and user-defined head shapes.
	noteheads="norm reg other reg reg other righttri"

music

1: c;d;2e;
bar

1: 2g;f;
bar

1: {b;a;g;}3;2c+;
bar

1: 1d;
bar

// do some shape overrides, both on group and note
1: [ hs "pie" ]2ce; [hs "isostri"] c e g hs "righttri";
endbar
```



8. TEXT STRINGS

Text strings are used in many different ways. A text string is enclosed in double quotes, and can contain any combination of letters, numbers, spaces, and punctuation. It can contain a \n to indicate a newline or \b to indicate a backspace, but otherwise cannot contain tabs or other control characters. If you want a double quote mark inside a string, it has to be preceded by a backslash, to indicate it is not ending the string:

```
"A \"word\" in quotes"
```

If you want an actual backslash in a string, it must be entered as two backslashes.

You can concatenate strings with a + sign. Thus the following are equivalent:

```
"this is a string"
"this is " + "a string"
```

8.1 Special characters

A string can also contain special music characters. These are specified by \(*xxx*), where the *xxx* is a code from the following table:

type	code	music symbol
clef	gclef	G clef (treble clef)
	fclef	F clef (bass clef)
	cclef	C clef (used for alto clef, tenor clef, etc.)
time sig	com	common time
	cut	cut time
accidental	flat	flat
	dblflat	double flat
	sharp	sharp
	dblsharp	double sharp
	nat	natural
note	4n	quarter (and shorter) note head
	2n	half note head
	1n	whole note
	dblwhole	double whole note
	dn2n	half note with stem down
	dn4n	quarter note with stem down
	dn8n	eighth note with stem down
	dn16n	16th note with stem down
	dn32n	32nd note with stem down
	dn64n	64th note with stem down
	dn128n	128th note with stem down
	dn256n	256th note with stem down
	up2n	half note with stem up
	up4n	quarter note with stem up
	up8n	eighth note with stem up
	up16n	16th note with stem up
	up32n	32nd note with stem up
	up64n	64th note with stem up
	up128n	128th note with stem up
	up256n	256th note with stem up

	upflag	upward flag
	dnflag	downward flag
notehead		
	xnote	X-shaped note head
	diamond	open diamond-shaped note head
	filldiamond	filled diamond-shaped note head
	dwhdiamond	double whole diamond-shaped note
	isostriangle	open isosceles triangle notehead
	fillisostriangle	filled isosceles triangle notehead
	dwhisostriangle	double whole isosceles triangle notehead
	piewedge	open piewedge notehead
	fillpiewedge	filled piewedge notehead
	dwhpiewedge	double whole piewedge notehead
	rectangle	open rectangle notehead
	fillrectangle	filled rectangle notehead
	dwhrectangle	double whole rectangle notehead
	righttriangle	open right triangle notehead
	fillrighttriangle	filled right triangle notehead
	dwhrighttriangle	double whole right triangle notehead
	urighttriangle	upside-down open right triangle notehead
	ufillrighttriangle	upside-down filled right triangle notehead
	udwhrighttriangle	upside-down double whole right triangle notehead
	semicircle	open semicircle notehead
	fillsemicircle	filled semicircle notehead
	dwhsemicircle	double whole semicircle notehead
	slashhead	open slash notehead
	fillslashhead	filled slash notehead
	dwhslashhead	double whole slash notehead
	blankhead	blank notehead
rest	qwhrest	quadruple whole rest
	dwhrest	double whole rest
	1rest	whole rest
	2rest	half rest
	4rest	quarter rest
	8rest	eighth rest
	16rest	sixteenth rest
	32rest	thirty-second rest
	64rest	sixty-fourth rest
	128rest	128th rest
	256rest	256th rest
pedal	begped	begin pedal mark
	endped	end pedal mark
	pedal	pedal up/down mark
ornaments	tr	trill
	mor	mordent
	invmor	inverted mordent
	turn	turn
	invturn	inverted turn

misc	ferm	fermata
	uferm	upside-down fermata
	acc_gt	accent like a greater-than sign
	acc_hat	accent like a "hat" (circumflex or "up-arrow")
	acc_uhat	accent like an upside down hat
	leg	legato mark
	dot	dot
	wedge	wedge
	uwedge	upside-down wedge
	sign	sign for D. S.
	coda	coda mark
	upbow	up bow
	dnbow	down bow
	rr	"railroad tracks" or caesura (2 slanted lines sometimes put at the top of a staff to indicate the end of a musical thought)
	measrpt	measure repeat
	copyright	C-in-circle copyright symbol
	dim	diminished
	halfdim	half diminished
	triangle	triangle

gclef	fclef	cclef	dblwhole	1n	2n	4n	upflag	dnflag	qwhrest	dwhrest
1rest	2rest	4rest	8rest	16rest	32rest	64rest	128rest	256rest	ll1rest	ll2rest
dot	nat	sharp	flat	dblsharp	dblflat	xnote	dwhdiamond	diamond	filldiamond	up2n
dn2n	up4n	dn4n	com	cut	begped	pedal	endped	dnbow	upbow	wedge
uwedge	ferm	uferm	sign	coda	mor	invmor	turn	invturn	acc_gt	acc_hat
acc_uhat	tr	leg	rr	dim	halfdim	triangle	measrpt	copyright	up8n	dn8n
up16n	dn16n	up32n	dn32n	up64n	dn64n	up128n	dn128n	up256n	dn256n	dwhrighttriangle
righttriangle	fillrighttriangle	udwhrighttriangle	urighttriangle	ufillrighttriangle	dwhrectangle	rectangle	fillrectangle	dwhisostriangle	isostriangle	fillisostriangle
dwhpiewedge	piewedge	fillpiewedge	dwhsemicircle	semicircle	fillsemicircle	dwhslashhead	slashhead	fillslashhead	blankhead	